



Additional Comments:

**\*\* Portion Below This Line To Be Filled Out by MoDOT \*\***

Comments: For CDG Engineers, Architects, Planners, Inc.

  
Submitted By Resident Engineer

4-12-11  
Date

Glenn A. Smith, P.E.

Comments: DBE Changes Noted. The contractor must make a good faith effort to meet the DBE Goal. The VE Approval does not authorize a lesser DBE Participation. MoDOT Bridge reviewed & Approved. Recommend APPROVAL.

Approval Recommended

Rejection Recommended

  
District Engineer

4/18/11  
Date

Comments: N/A

Approval Recommended

Rejection Recommended

Federal Highway Administration  
Required for FHWA Full Oversight Projects

Date

Comments: Approval is contingent on satisfactory results achieved in the field and written acknowledgement by the contractor that they are responsible for the consequences including unanticipated impacts or delays.

Approval

Rejection

State Construction and Materials Engineer

Date

Distribution: Resident Engineer, Project Manager, District Construction & Materials Engineer, State Construction & Materials Engineer, FHWA Value Engineering Administrator - MoDOT, P. O. Box 270, Jefferson City, MO 65102

City of Fenton  
 Old Highway 141 Bridge Value Engineering Proposal  
 Final VE Quantities  
 3/29/2011

Pay Item	Description	Units	Price	Unit Price	Plan Price	Rev	Qty	Plan Price	Rev	Diff
206-10.00	Class 1 Excavation	CY	759	\$25.00	\$18,975.00		640	\$25.00	\$16,000.00	(\$2,975.00)
206-10.03	Class 1 Excavation in Rock	CY	10	\$0.00	\$0.00		10	\$150.00	\$1,500.00	\$1,500.00
206-20.00	Class 2 Excavation	CY	101	\$0.00	\$0.00		101	\$25.00	\$2,525.00	\$2,525.00
206-21.00	Class 2 Excavation in Rock	CY	19	\$0.00	\$0.00		19	\$150.00	\$2,850.00	\$2,850.00
216-05.00	Removal of Bridge	LS	1	\$10,000.00	\$10,000.00		1	\$10,000.00	\$10,000.00	\$0.00
503-10.10	Bridge Approach Slab (Bridge)	SY	267	\$205.00	\$54,735.00		267	\$205.00	\$54,735.00	\$0.00
603-99.99	66" Precast Concrete Pipe Storm Sewer Adjustment	LS	1	\$4,500.00	\$4,500.00		1	\$4,500.00	\$4,500.00	\$0.00
702-10.12	Structural Steel Piles (12")	LF	1245	\$50.00	\$62,250.00		120	\$100.00	\$12,000.00	(\$50,250.00)
702-70.00	Pile Point Reinforcement	EA	83	\$105.00	\$8,715.00		6	\$630.00	\$3,780.00	(\$5,000.00)
703-20.03	Class B Concrete (Substructure)	CY	371	\$385.00	\$142,835.00		252.1	\$535.00	\$134,873.50	(\$7,961.50)
703-42.13	Slab on Prestressed Concrete Box Beam	SY	0	\$0.00	\$0.00		308	\$235.00	\$72,380.00	\$72,380.00
703-42.14	Class B-2 Concrete (Superstructure)	CY	56	\$500.00	\$28,000.00		0	\$0.00	\$0.00	(\$28,000.00)
705-60.50	Prestressed Concrete Box Beam (55 FT Span)	EA	12	\$12,500.00	\$150,000.00		7	\$18,150.00	\$127,050.00	(\$22,950.00)
710-00.00	Reinforcing Steel (Bridges)	LB	35990	\$0.90	\$32,391.00		18380	\$0.90	\$16,542.00	(\$15,849.00)
711-01.00	Reinforcing Steel (Epoxy Coated)	LB	10350	\$1.00	\$10,350.00		1410	\$1.00	\$1,410.00	(\$8,940.00)
712-23.00	Protective Coating-Concrete Bents (Urethane)	LS	1	\$10,000.00	\$10,000.00		0	\$10,000.00	\$0.00	(\$10,000.00)
715-10.01	Bridge Guard Rail	LF	128.33	\$175.00	\$22,457.75		117	\$175.00	\$20,475.00	(\$1,982.75)
716-10.00	Vertical Drain at End Bents	EA	2	\$3,300.00	\$6,600.00		2	\$3,300.00	\$6,600.00	\$0.00
716-10.02	Plain Neoprene Bearing Pad	EA	0	\$0.00	\$0.00		14	\$320.00	\$4,480.00	\$4,480.00
717-10.01	Laminated Neoprene Bearing Pad (P/S Structures)	EA	48	\$275.00	\$13,200.00		0	\$320.00	\$0.00	(\$13,200.00)
999-99.01	Performed Compression Expansion Joint Seal (1-5/8 In.)	LF	103	\$230.00	\$23,690.00		0	\$0.00	\$0.00	(\$23,690.00)
999-99.02	Bridge Design (Horner & Shiffrin)	LS	0	\$0.00	\$0.00		1	\$35,000.00	\$35,000.00	\$35,000.00
	Bridge Design Review (CDG)	LS	0	\$0.00	\$0.00		1	\$14,000.00	\$14,000.00	\$14,000.00
	<b>TOTALS</b>				<b>\$598,698.75</b>				<b>\$537,550.50</b>	<b>(\$61,148.25)</b>

NOTE: THESE VALUES REPRESENT THE REVISED BRIDGE PORTION OF THIS PROJECT. THERE IS NO CHANGE TO ANY OTHER CONTRACT ITEMS.

**DBE Utilization Form**  
**City of Fenton - Old Highway 141 Bridge**

DBE Name and Address	Bid Item Number	\$ Value of DBE Work	% of \$ Applicable	\$ Amount Applicable	% of Total Contract
ATK Safety Supply 6352 Cedar Springs Road Cedar Hill, MO 63016	6169901	\$9,789.00	100.00%	\$9,789.00	0.79%
	6169902				
	6206171A				
	6205900				
	6205901				
6205908					
Roden's Landscaping, Inc. 7800 Highway N O'Fallon, MO 63368	8022099	\$15,960.00	100.00%	\$15,960.00	1.30%
	8061099				
D & S Fencing Co. 2800 Sunnyside Road Festus, MO 63028	6061054	\$36,775.00	100.00%	\$36,775.00	2.99%
	6062300A				
	6062400				
	6063015				
	6069999				
	7122300				
Sabor, Inc. 1751 Ashby Road St. Louis, MO 63114	8181070	\$8,400.00	100.00%	\$8,400.00	0.68%
Bumpy's Steel Erection 327 Missouri Avenue Suite 516 East St. Louis, IL 62201	5031010	\$22,212.40	100.00%	\$22,212.40	1.80%
	7101000				
	7101000				
	7034214				
WW Petroleum P.O. Box 216 Macon, MO 63552	4011209	\$25,000.00	60.00%	\$15,000.00	1.22%
	4011213				
	4013010				
	4020520				
Eagle Distributors 27237 Roelker Road Unit A Wright City, MO 63034	7056050	\$102,699.00	60.00%	\$61,619.40	5.00%
	7261330				
	7261366				
	7311099				
	7320630				
	7320666				
	7261324				
	7261515				
	7311098				
	7320615				
7320624					
Silver Eagle Construction Products 400 S. Cool Springs Road P.O. Box 997 O'Fallon, MO 63366	5031010	\$7,388.00	60.00%	\$4,432.80	0.36%
	7021012				
	7027000				
	7161002				
Midwest Hauling and Contracting 2286 Rose Lane Pacific, MO 63069	7151001	\$3,750.00	100.00%	\$3,750.00	0.30%
	6181000	\$38,000.00	100.00%	\$38,000.00	3.08%
	3040504				
	4011209				
	4011213				
	4015010				
	4020520				
	7261330				
	7261336				
	7311099				
	7320630				
	7320666				
	6221001				
	7261324				
	7261515				
	7311098				
7320615					
7320624					
Blue Diamond Services, LLC 5850 Dulin Creek Road P.O. Box 242 House Springs, MO 63051	2035599	\$16,000.00	100.00%	\$16,000.00	1.30%
	6115099				

Windstar Transportation, LLC 111 Summit Place Webster Groves, MO 63119	6085007 6091051 6091060 6091098 6091099 5031010 7032003 7034214	\$4,621.60	100.00%	\$4,621.60	0.38%
<b>TOTALS</b>		<b>\$290,595.00</b>		<b>\$236,560.20</b>	<b>19.20%</b>

\*\*\*Sabur, Inc. has decided to pull off of this job due to their schedule being full and the difficulty of this project. I am including them as a DBE as they were previously approved and had a signed subcontract with us, but are not fulfilling their duties as a subcontractor on this project.

### STRUCTURE INVENTORY AND APPRAISAL SHEET

COUNTY St. Louis BRIDGE NO. 1420013 ROUTE: Old Highway 141

\*\*\*\*\*IDENTIFICATION\*\*\*\*\*

(1) STATE NAME Missouri CODE 297  
 (8) STRUCTURE NUMBER # 1420013  
 (5) INVENTORY ROUTE (ON/UNDER)- 152001410  
 (2) HIGHWAY AGENCY DISTRICT 06  
 (3) COUNTY CODE 096 (4) PLACE CODE 189  
 (6) FEATURES INTERSECTED Fenton Creek  
 (7) FACILITY CARRIED Old Highway 141  
 (9) LOCATION Section 3011, Township 44N, Range 5E  
 (11) MILEPOINT 0000000  
 (12) BASE HIGHWAY NETWORK CODE 0  
 (13) LRS INVENTORY ROUTE & SUBROUTE #  
 (16) LATITUDE 38 DEG 30 MIN 33 SEC  
 (17) LONGITUDE 90 DEG 26 MIN 01 SEC  
 (98) BORDER BRIDGE STATE CODE % SHARE \_\_\_\_\_ %  
 (99) BORDER BRIDGE STRUCTURE NO. # \_\_\_\_\_

SUFFICIENCY RATING = \_\_\_\_\_  
 STATUS = \_\_\_\_\_

\*\*\*\*\*CLASSIFICATION\*\*\*\*\*CODE

(112) NBIS BRIDGE LENGTH Y  
 (104) HIGHWAY SYSTEM 0  
 (26) FUNCTIONAL CLASS 17  
 (100) DEFENSE HIGHWAY 0  
 (101) PARALLEL STRUCTURE N  
 (102) DIRECTION OF TRAFFIC 2  
 (103) TEMPORARY STRUCTURE \_\_\_\_\_  
 (105) FEDERAL LANDS HIGHWAYS 0  
 (110) DESIGNATED NATIONAL NETWORK 0  
 (20) TOLL 3  
 (21) MAINTAIN 04  
 (22) OWNER City of Fenton  
 (37) HISTORICAL SIGNIFICANCE 5

\*\*\*\*\*STRUCTURE TYPE AND MATERIAL\*\*\*\*\*

(43) STRUCTURE TYPE MAIN: MATERIAL Prestressed Concrete  
 TYPE Girder CODE 506  
 (44) STRUCTURE TYPE APPR: MATERIAL \_\_\_\_\_  
 TYPE \_\_\_\_\_ CODE 000  
 (45) NUMBER OF SPANS IN MAIN UNIT 001  
 (46) NUMBER OF APPROACH SPANS 0000  
 (107) DECK STRUCTURE TYPE 2  
 (108) WEARING SURFACE/PROTECTIVE SYSTEM:  
 A) TYPE OF WEARING SURFACE \_\_\_\_\_ CODE 0  
 B) TYPE OF MEMBRANE \_\_\_\_\_ CODE 0  
 C) TYPE OF DECK PROTECTION \_\_\_\_\_ CODE 1

\*\*\*\*\*CONDITION\*\*\*\*\*CODE

(58) DECK 9  
 (59) SUPERSTRUCTURE 9  
 (60) SUBSTRUCTURE 9  
 (61) CHANNEL & CHANNEL PROTECTION 9  
 (62) CULVERTS N

\*\*\*\*\*LOAD RATING AND POSTING\*\*\*\*\*CODE

(31) DESIGN LOAD 6  
 (63) OPERATING RATING METHOD 1  
 (64) OPERATING RATING 90 tons  
 (65) INVENTORY RATING METHOD 1  
 (66) INVENTORY RATING 52 tons  
 (70) BRIDGE POSTING 5  
 (41) STRUCTURE OPEN, POSTED OR CLOSED G

\*\*\*\*\*AGE AND SERVICE\*\*\*\*\*

(27) YEAR BUILT 2011  
 (106) YEAR RECONSTRUCTED \_\_\_\_\_  
 (42) TYPE OF SERVICE: ON Highway  
 UNDER Waterway CODE 15  
 (28) LANES: ON STRUCTURE 03 UNDER STRUCTURE 00  
 (29) AVERAGE DAILY TRAFFIC 0010608  
 (30) YEAR OF ADT 2006 (109) TRUCK ADT \_\_\_\_\_  
 (19) BYPASS, DETOUR LENGTH 2.2 miles

\*\*\*\*\*APPRAISAL\*\*\*\*\*CODE

(67) STRUCTURAL EVALUATION 9  
 (68) DECK GEOMETRY 9  
 (69) UNDERCLEARANCES, VERTICAL & HORIZONTAL N  
 (71) WATERWAY ADEQUACY 4  
 (72) APPROACH ROADWAY ALIGNMENT 6  
 (36) TRAFFIC SAFETY FEATURES 1111  
 (113) SCOUR CRITICAL BRIDGES 8

\*\*\*\*\*GEOMETRIC DATA\*\*\*\*\*

(48) LENGTH OF MAXIMUM SPAN 55 FT.  
 (49) STRUCTURE LENGTH 000058 FT.  
 (50) CURB OR SIDEWALK: LEFT 00.0 FT. RIGHT 00.0 FT.  
 (51) BRIDGE ROADWAY WIDTH CURB TO CURB 48.00 FT.  
 (52) DECK WIDTH OUT TO OUT 48 FT.  
 (32) APPROACH ROADWAY WIDTH (2/SHOULDERS) 0048 FT.  
 (33) BRIDGE MEDIAN No median CODE 0  
 (34) SKEW 20 DEG (35) STRUCTURE FLARED 0  
 (10) INVENTORY ROUTE MIN VERT CLEAR 99 FT. 99 IN.  
 (47) INVENTORY ROUTE TOTAL HORIZ CLEAR 48.0 FT.  
 (53) MIN VERT CLEAR OVER BRIDGE RDWY 99 FT. 99 IN.  
 (54) MIN VERT UNDERCLEAR REF N \_\_\_\_\_ FT. IN.  
 (55) MIN LAT UNDERCLEAR RT REF N \_\_\_\_\_ FT.  
 (56) MIN LAT UNDERCLEAR LT REF N \_\_\_\_\_ FT.

\*\*\*\*\*PROPOSED IMPROVEMENTS\*\*\*\*\*

(75) TYPE OF WORK \_\_\_\_\_ CODE \_\_\_\_\_  
 (76) LENGTH OF STRUCTURE IMPROVEMENT \_\_\_\_\_ FT.  
 (94) BRIDGE IMPROVEMENT COST \$ \_\_\_\_\_,000  
 (95) ROADWAY IMPROVEMENT COST \$ \_\_\_\_\_,000  
 (96) TOTAL PROJECT COST \$ \_\_\_\_\_,000  
 (97) YEAR OF IMPROVEMENT COST ESTIMATE \_\_\_\_\_  
 (114) FUTURE ADT 015763  
 (115) YEAR OF FUTURE ADT 2026

\*\*\*\*\*NAVIGATION DATA\*\*\*\*\*

(38) NAVIGATION CONTROL \_\_\_\_\_ CODE N  
 (111) PIER PROTECTION \_\_\_\_\_ CODE 1  
 (39) NAVIGATION VERTICAL CLEARANCE 0000 FT.  
 (116) VERT-LIFT BRIDGE NAV MIN VERT CLEAR \_\_\_\_\_ FT.  
 (40) NAVIGATION HORIZONTAL CLEARANCE 00000 FT.

\*\*\*\*\*INSPECTIONS\*\*\*\*\*

(90) INSPECTION DATE \_\_\_\_/\_\_\_\_/\_\_\_\_ (91) FREQUENCY \_\_\_\_\_ MO  
 (92) CRITICAL FEATURE INSPECTION: (93) CFI DATE  
 A) FRACTURE CRIT DETAIL \_\_\_\_\_ MO A) \_\_\_\_/\_\_\_\_/\_\_\_\_  
 B) UNDERWATER INSP \_\_\_\_\_ MO B) \_\_\_\_/\_\_\_\_/\_\_\_\_  
 C) OTHER SPECIAL INSP \_\_\_\_\_ MO C) \_\_\_\_/\_\_\_\_/\_\_\_\_

**Prestressed Girder Ratings - Load Factor Method - Summary**  
*MODOT Bridge Inspection Rating Manual - Section 4*

**HS20 Truck:**

Inventory Rating =	51.7	Tons	>	36	Tons	<b>OKAY</b>
Operating Rating =	90.1	Tons				
Posting =	77.5	Tons	>	40	Tons	<b>No Posting Req'd</b>

---

**H20 Truck:**

Inventory Rating =	41.3	Tons	>	20	Tons	<b>OKAY</b>
Operating Rating =	72.0	Tons				
Posting =	61.9	Tons	>	23	Tons	<b>No Posting Req'd</b>

---


**3S2 Truck:**

Inventory Rating =	72.0	Tons	>	36.64	Tons	<b>OKAY</b>
Operating Rating =	125.5	Tons				
Posting =	108.0	Tons	>	40	Tons	<b>No Posting Req'd</b>

---

**MO5 Truck:** *(Commercial Zones Only)*


Inventory Rating =	61.3	Tons	>	36.64	Tons	<b>OKAY</b>
Operating Rating =	106.8	Tons				
Posting =	91.8	Tons	>	70	Tons	<b>No Posting Req'd</b>



3.31.2011

## RATING VEHICLE

Ratings are required at the inventory and operating levels by the load factor method on each bridge for the following vehicle.




(HS20 Truck)

**NOTE:** To convert to the MS loading, multiply the HS20 vehicle and axle weights by 0.9.

*See LPA Manual 3/23/2000  
IX-3 Item 3. SI & A Report*


## POSTING VEHICLES

Each bridge ~~designed below the HS20 level~~ should be checked to ensure proper posting. The following vehicles are established for this purpose. The H20 legal vehicle is used to model the load for single unit vehicles. The 3S2 vehicle is used as a model for all other vehicles. The MO5 vehicle is used to model the commercial zone loadings.




(H20 Legal Truck) (3 axle)

**Single Unit Vehicle (Legal Limit = 23 Tons)**



(3S2 Truck)

**All Other Vehicles (Legal Limit = 40 Tons)**



**Commercial Zone Vehicle (Limit = 70 Tons)**

### LIVE LOAD DISTRIBUTION FACTORS

Live load distribution factors in accordance with AASHTO's Standard Specifications for Highway Bridges, except as follows:

A.) The distribution factor for exterior steel stringers supporting concrete floors shall be determined by assuming the flooring to act as a simple span between stringers or beams when the spacing from the adjacent interior girders to the face of rail or edge of curb is less than 5'-6" and the overhang is less than 18". Also, this method of distribution may be used for any girder spacing when there is no overhang. The first wheel load shall be placed no farther than 2'-0" from the face of rail or roadway face of curb.

B.) The live load distribution factor for a one-lane loading for slab-type structures may be calculated assuming the distribution of two wheel loads over the roadway width not to exceed 24 feet.

### LOAD TESTING

Load testing of reinforced concrete bridges where the details of the reinforcement are unknown and an accurate loading history is not available will be permitted to establish load capacities. Allowable postings will be established at 75% of the proof load vehicle. The proof load vehicle shall be a single unit, 3-axle vehicle for short span bridges.

Load tests shall be performed by registered professional engineers. Load test reports shall include a description of how the test was performed, a summary of the gross weights, and axle weights and axle spacings of the vehicle used and the deflection under load.

**Project Data**

File: truck loads.CSP  
Project: Fenton Creek Rating Trucks  
Analysis Method: AASHTO Standard Specification  
User Job Number: 1100110  
State: FL  
State Job Number:  
Date: 3-30-11  
By: Leap  
Comments:

**CURRENT LOADS**

1.000\*(Truck) HS20  
1.000\*(Truck) H20  
1.000\*(Truck) 3S2  
1.000\*(Truck) MO5

**Standard Mode Options**

Truck Factors  
Moment 1.000  
Shear 1.000  
Deflection 1.000

Lane Factors  
Moment 1.000  
Shear 1.000  
Deflection 1.000

**Load Details**

## Truck Load Details

Name: HS20

Factor: 1.00

**Axles**

#	Mag, K	Min, ft	Max, ft
1	8.000		
2	32.000	14.000	14.000
3	32.000	14.000	30.000

## Truck Load Details

Name: H20

Factor: 1.00

**Axles**

#	Mag, K	Min, ft	Max, ft
1	8.000		
2	32.000	14.000	14.000

## Truck Load Details

Name: 3S2

Factor: 1.00

**Axles**

#	Mag, K	Min, ft	Max, ft
1	9.280		
2	16.000	12.000	12.000
3	16.000	3.792	3.792
4	16.000	23.417	23.417
5	16.000	3.792	3.792

Truck Load Details


Name: MO5  
Factor: 1.00

Axles

#	Mag, K	Min, ft	Max, ft
1	9.280		
2	16.000	12.000	12.000
3	16.000	23.417	23.417
4	16.000	3.792	3.792
5	16.000	3.792	3.792

ID: HS20  
 Type: Truck

Factors:  
 Moment: 1.000  
 Shear: 1.000  
 Deflection: 1.000



Span	Location (ft)	MOMENT (kft)		Corresponding Shear (K)		SHEAR (K)		Corresponding Moment (kft)		DEFLECT (in)
		(max)	(min)	(+)	(-)	(max)	(min)	(+)	(-)	(min)
1	0.000	0.000	-0.000	59.710	0.000	59.710	0.000	0.000	0.000	0.00
	5.500	289.200	0.000	52.582	0.000	52.582	0.000	289.200	0.000	57.43
	11.000	499.200	0.000	45.382	0.000	45.382	0.000	499.200	0.000	109.27
	16.500	630.000	0.000	38.182	0.000	38.182	0.000	630.000	0.000	150.11
	22.000	704.000	0.000	29.091	-2.909	30.982	17.455	681.600	0.000	175.30
	27.500	710.000	0.000	21.891	-21.891	23.855	-23.855	656.000	0.000	184.14
	33.000	704.000	0.000	2.909	-29.091	17.455	-17.455	576.000	0.000	175.30
	38.500	630.000	0.000	0.000	-38.182	11.055	-11.055	425.600	0.000	150.11
	44.000	499.200	0.000	0.000	-45.382	6.400	-6.400	281.600	0.000	109.27
	49.500	289.200	0.000	0.000	-52.582	3.200	-3.200	158.400	0.000	57.43
	55.000	0.000	-0.000	0.000	-59.710	0.000	0.000	0.000	-0.000	0.00
					0.000	-59.710	-59.710	0.000	-0.000	0.00


Support	Reaction	
	Positive	Negative
1	0.000	-59.782
2	0.000	-59.782

Moment causing bottom tension and Shear causing left-up/right-down are positive. Deflection down is positive. Reaction down is positive.

LEAP Software Tel:(800) 451-5327 Fax:(813) 980-3642 Net: www.leapsoft.com

ID: H20  
 Type: Truck

Factors:  
 Moment: 1.000  
 Shear: 1.000  
 Deflection: 1.000



Span	Location (ft)	MOMENT (kft)		Corresponding Shear (K)		SHEAR (K)		Corresponding Moment (kft)		DEFLECT (in)
		(max)	(min)	(+)	(-)	(max)	(min)	(+)	(-)	(max)
1	0.000	0.000	-0.000	37.924	0.000	37.924	0.000	0.000	0.000	0.00
	5.500	186.800	0.000	33.964	0.000	33.964	0.000	186.800	-0.000	34.74
	11.000	329.600	0.000	29.964	-2.036	29.964	0.000	329.600	0.000	66.33
	16.500	428.400	0.000	25.964	-6.036	25.964	0.000	428.400	0.000	91.60
	22.000	483.200	0.000	21.964	-10.036	21.964	0.000	483.200	0.000	107.80
	27.500	494.000	0.000	17.964	-17.964	17.964	0.000	494.000	0.000	113.16
	33.000	483.200	0.000	10.036	-21.964	13.964	0.000	460.800	0.000	107.80
	38.500	428.400	0.000	6.036	-25.964	9.964	0.000	383.600	0.000	91.60
	44.000	329.600	0.000	2.036	-29.964	6.400	0.000	281.600	0.000	66.33
	49.500	186.800	0.000	0.000	-33.964	3.200	0.000	158.400	0.000	34.74
	55.000	0.000	-0.000	0.000	-37.924	0.000	0.000	0.000	-0.000	0.00


Support	Reaction	
	Positive	Negative
1	0.000	-37.964
2	0.000	-37.964

Moment causing bottom tension and Shear causing left-up/right-down are positive. Deflection down is positive. Reaction down is positive.

LEAP Software Tel:(800) 451-5327 Fax:(813) 980-3642 Net: www.leapsoft.com

ID: 3S2  
 Type: Truck

Factors:  
 Moment: 1.000  
 Shear: 1.000  
 Deflection: 1.000



Span	Location (ft)	MOMENT (kft)		Corresponding Shear (K)		SHEAR (K)		Corresponding Moment (kft)		DEFLECT (in)		
		(max)	(min)	(+)	(-)	(max)	(min)	(+)	(-)	(max)	(min)	
1	0.000	0.000	-0.000	47.915	0.000	47.915	0.000	0.000	-0.000	0.00	0.00	
	5.500	223.632	0.000	40.660	0.000	0.000	0.000	223.632	0.000	43.27	0.00	
	11.000	366.656	0.000	33.332	0.000	33.332	0.000	366.656	0.000	81.83	0.00	
	16.500	470.832	0.000	26.004	0.000	26.764	0.000	441.600	0.000	111.83	0.00	
	22.000	518.968	0.000	7.728	-8.272	21.000	0.000	462.011	0.000	129.91	0.00	
	27.500	498.993	0.000	15.600	-15.600	15.600	0.000	498.993	0.000	135.09	0.00	
	33.000	518.968	0.000	8.272	-7.728	11.697	0.000	386.000	0.000	129.91	0.00	
	38.500	470.832	0.000	0.000	-26.004	8.497	0.000	327.133	0.000	111.83	0.00	
	44.000	366.656	0.000	0.000	-33.332	5.297	0.000	233.067	0.000	81.83	0.00	
	49.500	223.632	0.000	0.000	-40.660	2.097	0.000	103.800	0.000	43.27	0.00	
	55.000	0.000	0.000	0.000	-47.915	0.000	0.000	0.000	-0.000	0.00	0.00	
			-0.000	0.000	0.000	-47.915	-47.915	0.000	0.000	0.000	0.00	0.00


Support	Reaction	
	Positive	Negative
1	0.000	-47.988
2	0.000	-47.988

Moment causing bottom tension and Shear causing left-up/right-down are positive. Deflection down is positive. Reaction down is positive.

LEAP Software Tel:(800) 451-5327 Fax:(813) 980-3642 Net: www.leapsoft.com

ID: M05  
 Type: Truck

Factors:  
 Moment: 1.000  
 Shear: 1.000  
 Deflection: 1.000



Span	Location (ft)	MOMENT (kft)		Corresponding Shear (K)		SHEAR (K)		Corresponding Moment (kft)		DEFLECT (in)	
		(max)	(min)	(+)	(-)	(max)	(min)	(+)	(-)	(max)	(min)
1	0.000	0.000	-0.000	53.624	0.000	53.624	0.000	0.000	0.000	0.00	0.00
	5.500	255.032	0.000	46.369	0.000	46.369	0.000	255.032	0.000	47.41	0.00
	11.000	429.456	0.000	39.041	0.000	39.041	0.000	429.456	0.000	90.00	0.00
	16.500	547.933	0.000	20.885	0.000	20.885	0.000	547.933	0.000	123.33	0.00
	22.000	610.000	0.000	14.485	-1.515	14.485	-1.515	610.000	0.000	143.36	0.00
	27.500	601.666	0.000	19.503	-19.503	19.503	-19.503	601.666	0.000	148.47	0.00
	33.000	610.000	0.000	1.515	-14.485	1.515	-14.485	610.000	0.000	143.36	0.00
	38.500	547.933	0.000	0.000	-20.885	0.000	-20.885	547.933	0.000	123.33	0.00
	44.000	429.456	0.000	0.000	-39.041	0.000	-39.041	429.456	0.000	90.00	0.00
	49.500	255.032	0.000	0.000	-46.369	0.000	-46.369	255.032	0.000	47.41	0.00
	55.000	0.000	0.000	0.000	-53.624	0.000	-53.624	0.000	-0.000	0.00	0.00

Support	Reaction	
	Positive	Negative
1	0.000	-53.697
2	0.000	-53.697

Moment causing bottom tension and Shear causing left-up/right-down are positive. Deflection down is positive. Reaction down is positive.

TITLE:

SUBJECT FILE FENRON CREEK

RATING - LIVE LOAD

BY TPL DATE 3.30.11 CHECKED \_\_\_\_\_ DATE \_\_\_\_\_

$$\text{Impact} = \frac{50}{L+125} = \frac{50}{55+125} = 0.28$$

<u>truck</u>	<u>Moment from Consys</u>	<u>x Impact = 1.28 =</u>	<u>Input for spreadsheet</u>
H520	710 k.ft		909 k.ft
H20	494 k.ft		632 k.ft
3S2	519 k.ft		664 k.ft
MOS	610 k.ft		781 k.ft

**Prestressed Girder Ratings - Load Factor Method**

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = HS20

**Material Properties:**

Concrete:

f'c\* = 7000 psi  
f'ci\* = 5500 psi  
f'c = 4000 psi  
Ec\* = 5072 ksi  
Eci\* = 4496 ksi  
Ec = 3834 ksi  
n = 5.52

Prestressing Steel:

f's' = 270 ksi  
E\_s' = 28000 ksi

Reinforcing Steel

f\_y = 60 ksi  
E\_s = 29000 ksi  
n = 7.56

**Girder Geometry and Strand Locations:**

Girder Properties from Conspan:

A = 696 in<sup>2</sup>  
Y\_b = 10.5 in  
I = 34529 in<sup>4</sup>  
d = 21 in  
b\_top = 48 in  
b\_eff = 68 in (exterior girder)  
t\_s = 7.5 in  
A\_smidspan = 0.248 in<sup>2</sup>/ft (#5 @ 15")  
Area of Slab Steel / ft

Strands:

# of Strands = 30  
A\_s/strand = \_\_\_\_\_ in<sup>2</sup>  
Y\_center = 3.62 in  
Y\_ends = 3.62 in

Haunch Heights:

Mid Span = 1.00 in (assume for simplification)  
End = 3.25 in

Prestressing Pattern:

d (in)	Str. @ Center	Str. @ Ends
1.75	14	14
3.75	14	14
5.75	0	0
7.75	0	0
9.75	0	0
11.75	0	0
13.75	0	0
15.75	2	2
20		0
22		0
24		0
26		0
28		0
30		0
32		0
34		0
Total	30	30

Prestress Loss = 25.90%  
F\_i = 43.90 k  
F\_f = 975.90 k  
e\_c = 6.88 in

= Total prestress loss (Ext Girder) per Conspan  
= 0.75\*270ksi\*0.217in<sup>2</sup>

## Prestressed Girder Ratings - Load Factor Method

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = HS20

### Section Properties for Girder Only near Mid Span (For Dead Load):

# Strands	A (in <sup>2</sup> )	y (in)	Ay (in <sup>3</sup> )	d (in)	I <sub>o</sub> (in <sup>4</sup> )	Ad <sup>2</sup> (in <sup>4</sup> )	I (in <sup>4</sup> )
14	13.732	1.75	24.032	8.47	-	985.36	985.36
14	13.732	3.75	51.497	6.47	-	574.99	574.99
0	0.000	5.75	0.000	4.47	-	0.00	0.00
0	0.000	7.75	0.000	2.47	-	0.00	0.00
0	0.000	9.75	0.000	0.47	-	0.00	0.00
0	0.000	11.75	0.000	1.53	-	0.00	0.00
0	0.000	13.75	0.000	3.53	-	0.00	0.00
2	1.962	15.75	30.898	5.53	-	59.98	59.98
Girder	696	10.5	7308.0	0.28	34529	54.26	34583
P. Steel	29.427		106.4			1620.3	1620
Σ	725.43		7414.4				36204

$$Y_b = 10.22 \text{ in}$$

$$Y_t = 10.78 \text{ in}$$

$$I = 36204 \text{ in}^4$$

$$S_b = 3542.2 \text{ in}^3$$

$$S_t = 3358.6 \text{ in}^3$$

### Section Properties for Girder and Slab near Mid Span:

$$n = 1.32 \text{ concrete}$$

$$n = 5.72 \text{ steel}$$

# Strands	A (in <sup>2</sup> )	y (in)	Ay (in <sup>3</sup> )	d (in)	I <sub>o</sub> (in <sup>4</sup> )	Ad <sup>2</sup> (in <sup>4</sup> )	I (in <sup>4</sup> )
14	13.73	1.75	24.032	14.11	-	2734.329	2734.329
14	13.73	3.75	51.497	12.11	-	2014.154	2014.154
0	0.00	5.75	0.000	10.11	-	0	0
0	0.00	7.75	0.000	8.11	-	0	0
0	0.00	9.75	0.000	6.11	-	0	0
0	0.00	11.75	0.000	4.11	-	0	0
0	0.00	13.75	0.000	2.11	-	0	0
2	1.96	15.75	30.898	0.11	-	0.024069	0.024069
Girder	696.00	10.50	7308.00	5.36	34529.0	20001.5	54530.5
Haunch	36.28	21.50	780.12	5.64	3.02	1153.9	1156.9
Slab Steel	6.63	27.06	179.39	11.20	-	831.5	831.5
Slab	385.52	25.75	9927.24	9.89	1807.14	37703.0	39510.2
P. Steel	29.43	-	106.43	-	-	4748.5	4748.5
Σ	1153.86		18301.2				100778

$$Y_b = 15.86 \text{ in}$$

$$Y_t = 5.14 \text{ in}$$

$$Y_{\text{slab}} = 13.64 \text{ in}$$

$$I = 100778 \text{ in}^4$$

$$S_b' = 6353.9 \text{ in}^3$$

$$S_t' = 19609.5 \text{ in}^3$$

Slab Steel Height (y) =  
21+1+3+1+.75+.5\*.625 = 27.06"

**Prestressed Girder Ratings - Load Factor Method**

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = HS20

**Section Properties for Girder and Slab near Mid Span:(Creep Considered - 3n)**

n = 1.32 concrete  
n = 5.72 steel

# Strands	A (in <sup>2</sup> )	y (in)	Ay (in <sup>3</sup> )	d (in)	I <sub>o</sub> (in <sup>4</sup> )	Ad <sup>2</sup> (in <sup>4</sup> )	I (in <sup>4</sup> )
14	13.73	1.75	24.032	11.04	-	1674.305	1674.305
14	13.73	3.75	51.497	9.04	-	1122.706	1122.706
0	0.00	5.75	0.000	7.04	-	0	0
0	0.00	7.75	0.000	5.04	-	0	0
0	0.00	9.75	0.000	3.04	-	0	0
0	0.00	11.75	0.000	1.04	-	0	0
0	0.00	13.75	0.000	0.96	-	0	0
2	1.96	15.75	30.898	2.96	-	17.16669	17.16669
Girder	696.00	10.50	7308.00	2.29	34529.0	3655.9	38184.9
Haunch	12.09	21.50	260.04	8.71	1.01	917.2	918.2
Slab Steel	6.63	27.06	179.39	14.27	-	1349.6	1349.6
Slab	128.51	25.75	3309.08	12.96	602.38	21578.2	22180.6
P. Steel	29.43	-	106.43	-	-	2814.2	2814.2
Σ	872.66		11162.9				65447

Y<sub>b</sub> = 12.79 in  
Y<sub>t</sub> = 8.21 in  
Y<sub>slab</sub> = 16.71 in  
I = 65447 in<sup>4</sup>  
S<sub>b</sub>" = 5116.3 in<sup>3</sup>  
S<sub>t</sub>" = 7973.5 in<sup>3</sup>

**Ultimate Strength Analysis:**

d = 25.88 in  
ρ\* = 0.00370  
β<sub>1</sub> = 0.7  
f<sub>su</sub>\* = 231.55 ksi      f'c = 4 ksi  
φ M<sub>n</sub> = 2833.69 k-ft      Impact = 0.278

	Interior	Exterior	
M <sub>DL</sub> =	574.5	553.1	k-ft
M <sub>SDL</sub> =	90.8	90.8	k-ft
M <sub>LL+I</sub> =	605	570	k-ft
M <sub>PED</sub> =	0	0	k-ft
RF(w/o Ped) =	1.50	1.61	
RF(w/ Ped) =	2.00	2.15	
RF <sub>min</sub> =	1.50		

Trk Wt =	36	Ton
M <sub>LL+I</sub> =	907.2	k-ft
M <sub>LL+I</sub> per Consys * Impact		
	Interior	Exterior
DF =	0.6666	0.6286
M <sub>ped</sub> =	0	k-ft

Distribution Factors are Per Truck per AASHTO 3.23.2.3.2

**Prestressed Girder Ratings - Load Factor Method**

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = HS20

	Interior		Exterior		
	LIVE	L + Ped	LIVE	L + Ped	
$0.6 f'_c =$	4.20	4.20	4.20	4.20	ksi
$0.4 f'_c =$	2.80	2.80	2.80	2.80	ksi
$f_{Prestress} =$	-0.60	-0.60	-0.60	-0.60	ksi
$f_{DL} =$	2.05	2.05	1.98	1.98	ksi
$f_{SDL} =$	0.14	0.14	0.14	0.14	ksi
$f_{Ped} =$	0.00	0.00	0.00	0.00	ksi
$f_{LL+I} =$	0.37	0.37	0.35	0.35	ksi
<b>RF =</b>	<b>7.05</b>	<b>9.40</b>	<b>7.69</b>	<b>10.26</b>	ksi Full Loading
<b>RF =</b>	<b>5.42</b>	<b>7.22</b>	<b>5.85</b>	<b>7.80</b>	ksi Live + 0.5(pre + D)

**RF<sub>min</sub> = 5.42**

	Interior		Exterior		
	LIVE	L + P	LIVE	L + P	
$6 (f'_c)^{1/2} =$	0.50	0.50	0.50	0.50	ksi
$f_{Prestress} =$	-3.30	-3.30	-3.30	-3.30	ksi
$f_{DL} =$	1.95	1.95	1.87	1.87	ksi
$f_{SDL} =$	0.21	0.21	0.21	0.21	ksi
$f_{Ped} =$	0.00	0.00	0.00	0.00	ksi
$f_{LL+I} =$	1.14	1.14	1.08	1.08	ksi
<b>RF =</b>	<b>1.44</b>	<b>1.92</b>	<b>1.59</b>	<b>2.12</b>	ksi

**RF<sub>min</sub> = 1.44**

**RF<sub>min</sub> = 1.44**  
Inventory = **51.7** Ton

Int. Ext.  
RF = 2.50 2.69 Both are done with Pedestrian Loading  
Operating = **90.1** Ton

Posted = **77.5** Ton

HS20 Truck		
Inventory =	<b>51.7</b>	Tons
Operating =	<b>90.1</b>	Tons
Posted =	<b>77.5</b>	Tons

## Prestressed Girder Ratings - Load Factor Method

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = H20

### Material Properties:

#### Concrete:

$f'c^* = 7000$  psi  
 $f'ci^* = 5500$  psi  
 $f'c = 4000$  psi  
 $Ec^* = 5072$  ksi  
 $Eci^* = 4496$  ksi  
 $Ec = 3834$  ksi  
 $n = 5.52$

#### Prestressing Steel:

$f_s' = 270$  ksi  
 $E_s' = 28000$  ksi

#### Reinforcing Steel

$f_y = 60$  ksi  
 $E_s = 29000$  ksi  
 $n = 7.56$

### Girder Geometry and Strand Locations:

#### Girder Properties from Conspan:

$A = 696$  in<sup>2</sup>  
 $Y_b = 10.5$  in  
 $I = 34529$  in<sup>4</sup>  
 $d = 21$  in  
 $b_{top} = 48$  in  
 $b_{eff} = 68$  in  
 $t_s = 7.5$  in  
 $A_{smidspan} = 0.248$  in<sup>2</sup>/ft  
Area of Slab Steel / ft

#### Strands:

# of Strands = 30  
 $A_{s/strand} = 0.217$  in<sup>2</sup>  
 $Y_{center} = 3.62$  in  
 $Y_{ends} = 3.62$  in

#### Haunch Heights:

Mid Span = 1.00 in  
End = 3.25 in

#### Prestressing Pattern:

d (in)	Str. @ Center	Str. @ Ends
1.75	14	14
3.75	14	14
5.75	0	0
7.75	0	0
9.75	0	0
11.75	0	0
13.75	0	0
15.75	2	2
20	0	0
22	0	0
24	0	0
26	0	0
28	0	0
30	0	0
32	0	0
34	0	0
Total	30	30

Prestress Loss = 25.90%  
 $F_i = 43.9$  k  
 $F_f = 975.897$  k  
 $ec = 6.88$  in

## Prestressed Girder Ratings - Load Factor Method

*MODOT Bridge Inspection Rating Manual - Section 4*

Truck Type = H20

### Section Properties for Girder Only near Mid Span (For Dead Load):

# Strands	A (in <sup>2</sup> )	y (in)	Ay (in <sup>3</sup> )	d (in)	I <sub>o</sub> (in <sup>4</sup> )	Ad <sup>2</sup> (in <sup>4</sup> )	I (in <sup>4</sup> )
14	13.732	1.75	24.032	8.47	-	985.36	985.36
14	13.732	3.75	51.497	6.47	-	574.99	574.99
0	0.000	5.75	0.000	4.47	-	0.00	0.00
0	0.000	7.75	0.000	2.47	-	0.00	0.00
0	0.000	9.75	0.000	0.47	-	0.00	0.00
0	0.000	11.75	0.000	1.53	-	0.00	0.00
0	0.000	13.75	0.000	3.53	-	0.00	0.00
2	1.962	15.75	30.898	5.53	-	59.98	59.98
Girder	696	10.5	7308.0	0.28	34529	54.26	34583
P. Steel	29.427		106.4			1620.3	1620
Σ	725.43		7414.4				36204

$$Y_b = 10.22 \text{ in}$$

$$Y_t = 10.78 \text{ in}$$

$$I = 36204 \text{ in}^4$$

$$S_b = 3542.2 \text{ in}^3$$

$$S_t = 3358.6 \text{ in}^3$$

### Section Properties for Girder and Slab near Mid Span:

$$n = 1.32 \text{ concrete}$$

$$n = 5.72 \text{ steel}$$

# Strands	A (in <sup>2</sup> )	y (in)	Ay (in <sup>3</sup> )	d (in)	I <sub>o</sub> (in <sup>4</sup> )	Ad <sup>2</sup> (in <sup>4</sup> )	I (in <sup>4</sup> )
14	13.73	1.75	24.032	14.11	-	2734.329	2734.329
14	13.73	3.75	51.497	12.11	-	2014.154	2014.154
0	0.00	5.75	0.000	10.11	-	0	0
0	0.00	7.75	0.000	8.11	-	0	0
0	0.00	9.75	0.000	6.11	-	0	0
0	0.00	11.75	0.000	4.11	-	0	0
0	0.00	13.75	0.000	2.11	-	0	0
2	1.96	15.75	30.898	0.11	-	0.024069	0.024069
Girder	696.00	10.50	7308.00	5.36	34529.0	20001.5	54530.5
Haunch	36.28	21.50	780.12	5.64	3.02	1153.9	1156.9
Slab Steel	6.63	27.06	179.39	11.20	-	831.5	831.5
Slab	385.52	25.75	9927.24	9.89	1807.14	37703.0	39510.2
P. Steel	29.43	-	106.43	-	-	4748.5	4748.5
Σ	1153.86		18301.2				100778

$$Y_b = 15.86 \text{ in}$$

$$Y_t = 5.14 \text{ in}$$

$$Y_{t\text{slab}} = 13.64 \text{ in}$$

$$I = 100778 \text{ in}^4$$

$$S_b' = 6353.9 \text{ in}^3$$

$$S_t' = 19609.5 \text{ in}^3$$

**Prestressed Girder Ratings - Load Factor Method**

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = H20

**Section Properties for Girder and Slab near Mid Span:(Creep Considered - 3n)**

n = 1.32 concrete  
n = 5.72 steel

# Strands	A (in <sup>2</sup> )	y (in)	Ay (in <sup>3</sup> )	d (in)	I <sub>o</sub> (in <sup>4</sup> )	Ad <sup>2</sup> (in <sup>4</sup> )	I (in <sup>4</sup> )
14	13.73	1.75	24.032	11.04	-	1674.305	1674.305
14	13.73	3.75	51.497	9.04	-	1122.706	1122.706
0	0.00	5.75	0.000	7.04	-	0	0
0	0.00	7.75	0.000	5.04	-	0	0
0	0.00	9.75	0.000	3.04	-	0	0
0	0.00	11.75	0.000	1.04	-	0	0
0	0.00	13.75	0.000	0.96	-	0	0
2	1.96	15.75	30.898	2.96	-	17.16669	17.16669
Girder	696.00	10.50	7308.00	2.29	34529.0	3655.9	38184.9
Haunch	12.09	21.50	260.04	8.71	1.01	917.2	918.2
Slab Steel	6.63	27.06	179.39	14.27	-	1349.6	1349.6
Slab	128.51	25.75	3309.08	12.96	602.38	21578.2	22180.6
P. Steel	29.43	-	106.43	-	-	2814.2	2814.2
Σ	872.66		11162.9				65447

Y<sub>b</sub> = 12.79 in  
Y<sub>t</sub> = 8.21 in  
Y<sub>slab</sub> = 16.71 in  
I = 65447 in<sup>4</sup>  
S<sub>b</sub>" = 5116.3 in<sup>3</sup>  
S<sub>t</sub>" = 7973.5 in<sup>3</sup>

**Ultimate Strength Analysis:**

d = 25.88 in  
ρ\* = 0.00370  
β<sub>1</sub> = 0.7  
f<sub>su</sub>\* = 231.55 ksi      f'<sub>c</sub> = 4 ksi  
φ M<sub>n</sub> = 2833.69 k-ft      Impact = 0.278

	Interior	Exterior		Trk Wt = 20 Ton
M <sub>DL</sub> =	574.5	553.1	k-ft	M <sub>LL+I</sub> = 631.2 k-ft
M <sub>SDL</sub> =	90.8	90.8	k-ft	M <sub>LL+I</sub> per Consys * Impact
M <sub>LL+I</sub> =	421	397	k-ft	Interior
M <sub>PED</sub> =	0	0	k-ft	DF = 0.6666      0.6286
RF(w/o Ped) =	2.16	2.32		Mped = 0 k-ft
RF(w/ Ped) =	2.88	3.10		
	RF <sub>min</sub> = 2.16			

Distribution Factors are Per Truck per AASHTO 3.23.2.3.2

**Prestressed Girder Ratings - Load Factor Method**

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = H20

	Interior		Exterior		
	LIVE	L + Ped	LIVE	L + Ped	
$0.6 f'_c =$	4.20	4.20	4.20	4.20	ksi
$0.4 f'_c =$	2.80	2.80	2.80	2.80	ksi
$f_{Prestress} =$	-0.60	-0.60	-0.60	-0.60	ksi
$f_{DL} =$	2.05	2.05	1.98	1.98	ksi
$f_{SDL} =$	0.14	0.14	0.14	0.14	ksi
$f_{Ped} =$	0.00	0.00	0.00	0.00	ksi
$f_{LL+I} =$	0.26	0.26	0.24	0.24	ksi
<b>RF =</b>	<b>10.13</b>	<b>13.51</b>	<b>11.06</b>	<b>14.75</b>	ksi Full Loading
<b>RF =</b>	<b>7.78</b>	<b>10.38</b>	<b>8.41</b>	<b>11.22</b>	ksi Live + 0.5(pre + D)

**RF<sub>min</sub> = 7.78**

	Interior		Exterior		
	LIVE	L + P	LIVE	L + P	
$6 (f'_c)^{1/2} =$	0.50	0.50	0.50	0.50	ksi
$f_{Prestress} =$	-3.30	-3.30	-3.30	-3.30	ksi
$f_{DL} =$	1.95	1.95	1.87	1.87	ksi
$f_{SDL} =$	0.21	0.21	0.21	0.21	ksi
$f_{Ped} =$	0.00	0.00	0.00	0.00	ksi
$f_{LL+I} =$	0.79	0.79	0.75	0.75	ksi
<b>RF =</b>	<b>2.07</b>	<b>2.75</b>	<b>2.29</b>	<b>3.05</b>	ksi

**RF<sub>min</sub> = 2.07**

**RF<sub>min</sub> = 2.07**  
**Inventory = 41.3 Ton**

Int. Ext.  
**RF = 3.60 3.87** Both are done with Pedestrian Loading  
**Operating = 72.0 Ton**

**Posted = 61.9 Ton**

H20 Truck		
Inventory =	<b>41.3</b>	Tons
Operating =	<b>72.0</b>	Tons
Posted =	<b>61.9</b>	Tons

**Prestressed Girder Ratings - Load Factor Method**

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = 3S2

**Material Properties:**

Concrete:

f'c\* = 7000 psi  
f'ci\* = 5500 psi  
f'c = 4000 psi  
Ec\* = 5072 ksi  
Eci\* = 4496 ksi  
Ec = 3834 ksi  
n = 5.52

Prestressing Steel:

f's' = 270 ksi  
E\_s' = 28000 ksi

Reinforcing Steel

f\_y = 60 ksi  
E\_s = 29000 ksi  
n = 7.56

**Girder Geometry and Strand Locations:**

Girder Properties from Conspan:

A = 696 in<sup>2</sup>  
Y<sub>b</sub> = 10.5 in  
I = 34529 in<sup>4</sup>  
d = 21 in  
b<sub>top</sub> = 48 in  
b<sub>eff</sub> = 68 in  
t<sub>s</sub> = 7.5 in  
A<sub>smidspan</sub> = 0.248 in<sup>2</sup>/ft  
Area of Slab Steel / ft

Strands:

# of Strands = 30  
A<sub>s/strand</sub> = 0.217 in<sup>2</sup>  
Y<sub>center</sub> = 3.62 in  
Y<sub>ends</sub> = 3.62 in

Haunch Heights:

Mid Span = 1.00 in  
End = 3.25 in

Prestressing Pattern:

d (in)	Str. @ Center	Str. @ Ends
1.75	14	14
3.75	14	14
5.75	0	0
7.75	0	0
9.75	0	0
11.75	0	0
13.75	0	0
15.75	2	2
20	0	0
22	0	0
24	0	0
26	0	0
28	0	0
30	0	0
32	0	0
34	0	0
Total	30	30

Prestress Loss = 25.90%  
F<sub>i</sub> = 43.9 k  
F<sub>f</sub> = 975.897 k  
e<sub>c</sub> = 6.88 in

**Prestressed Girder Ratings - Load Factor Method**

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = 3S2

**Section Properties for Girder Only near Mid Span (For Dead Load):**

# Strands	A (in <sup>2</sup> )	y (in)	Ay (in <sup>3</sup> )	d (in)	I <sub>o</sub> (in <sup>4</sup> )	Ad <sup>2</sup> (in <sup>4</sup> )	I (in <sup>4</sup> )
14	13.732	1.75	24.032	8.47	-	985.36	985.36
14	13.732	3.75	51.497	6.47	-	574.99	574.99
0	0.000	5.75	0.000	4.47	-	0.00	0.00
0	0.000	7.75	0.000	2.47	-	0.00	0.00
0	0.000	9.75	0.000	0.47	-	0.00	0.00
0	0.000	11.75	0.000	1.53	-	0.00	0.00
0	0.000	13.75	0.000	3.53	-	0.00	0.00
2	1.962	15.75	30.898	5.53	-	59.98	59.98
Girder	696	10.5	7308.0	0.28	34529	54.26	34583
P. Steel	29.427		106.4			1620.3	1620
Σ	725.43		7414.4				36204

$Y_b = 10.22$  in  
 $Y_t = 10.78$  in  
 $I = 36204$  in<sup>4</sup>  
 $S_b = 3542.2$  in<sup>3</sup>  
 $S_t = 3358.6$  in<sup>3</sup>

**Section Properties for Girder and Slab near Mid Span:**

$n = 1.32$   
 $n = 5.72$

# Strands	A (in <sup>2</sup> )	y (in)	Ay (in <sup>3</sup> )	d (in)	I <sub>o</sub> (in <sup>4</sup> )	Ad <sup>2</sup> (in <sup>4</sup> )	I (in <sup>4</sup> )
14	13.73	1.75	24.032	14.11	-	2734.329	2734.329
14	13.73	3.75	51.497	12.11	-	2014.154	2014.154
0	0.00	5.75	0.000	10.11	-	0	0
0	0.00	7.75	0.000	8.11	-	0	0
0	0.00	9.75	0.000	6.11	-	0	0
0	0.00	11.75	0.000	4.11	-	0	0
0	0.00	13.75	0.000	2.11	-	0	0
2	1.96	15.75	30.898	0.11	-	0.024069	0.024069
Girder	696.00	10.50	7308.00	5.36	34529.0	20001.5	54530.5
Haunch	36.28	21.50	780.12	5.64	3.02	1153.9	1156.9
Slab Steel	6.63	27.06	179.39	11.20	-	831.5	831.5
Slab	385.52	25.75	9927.24	9.89	1807.14	37703.0	39510.2
P. Steel	29.43	-	106.43	-	-	4748.5	4748.5
Σ	1153.86		18301.2				100778

$Y_b = 15.86$  in  
 $Y_t = 5.14$  in  
 $Y_{t\text{slab}} = 13.64$  in  
 $I = 100778$  in<sup>4</sup>  
 $S_b' = 6353.9$  in<sup>3</sup>  
 $S_t' = 19609.5$  in<sup>3</sup>

**Prestressed Girder Ratings - Load Factor Method**

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = 3S2

**Section Properties for Girder and Slab near Mid Span:(Creep Considered - 3n)**

n = 1.32 concrete  
n = 5.72 steel

# Strands	A (in <sup>2</sup> )	y (in)	Ay (in <sup>3</sup> )	d (in)	I <sub>c</sub> (in <sup>4</sup> )	Ad <sup>2</sup> (in <sup>4</sup> )	I (in <sup>4</sup> )
14	13.73	1.75	24.032	11.04	-	1674.305	1674.305
14	13.73	3.75	51.497	9.04	-	1122.706	1122.706
0	0.00	5.75	0.000	7.04	-	0	0
0	0.00	7.75	0.000	5.04	-	0	0
0	0.00	9.75	0.000	3.04	-	0	0
0	0.00	11.75	0.000	1.04	-	0	0
0	0.00	13.75	0.000	0.96	-	0	0
2	1.96	15.75	30.898	2.96	-	17.16669	17.16669
Girder	696.00	10.50	7308.00	2.29	34529.0	3655.9	38184.9
Haunch	12.09	21.50	260.04	8.71	1.01	917.2	918.2
Slab Steel	6.63	27.06	179.39	14.27	-	1349.6	1349.6
Slab	128.51	25.75	3309.08	12.96	602.38	21578.2	22180.6
P. Steel	29.43	-	106.43	-	-	2814.2	2814.2
Σ	872.66		11162.9				65447

Y<sub>b</sub> = 12.79 in  
Y<sub>t</sub> = 8.21 in  
Y<sub>tslab</sub> = 16.71 in  
I = 65447 in<sup>4</sup>  
S<sub>b</sub>" = 5116.3 in<sup>3</sup>  
S<sub>t</sub>" = 7973.5 in<sup>3</sup>

**Ultimate Strength Analysis:**

d = 25.88 in  
ρ\* = 0.00370  
β<sub>1</sub> = 0.7  
f<sub>su</sub>\* = 231.55 ksi      f'<sub>c</sub> = 4 ksi  
φ M<sub>n</sub> = 2833.69 k-ft      Impact = 0.278

	Interior	Exterior		Trk Wt = 36.64 Ton
M <sub>DL</sub> =	574.5	553.1	k-ft	M <sub>LL+I</sub> = 663.1 k-ft
M <sub>SDL</sub> =	90.8	90.8	k-ft	M <sub>LL+I</sub> per Consys * Impact
M <sub>LL+I</sub> =	442	417	k-ft	Interior      Exterior
M <sub>PED</sub> =	0	0	k-ft	DF = 0.6666      0.6286
RF(w/o Ped) =	2.05	2.21		Mped = 0      k-ft
RF(w/ Ped) =	2.74	2.95		
	RF <sub>min</sub> =	2.05		

Distribution Factors are Per Truck per AASHTO 3.23.2.3.2

**Prestressed Girder Ratings - Load Factor Method**

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = 3S2

	Interior		Exterior		
	LIVE	L + Ped	LIVE	L + Ped	
$0.6 f'_c =$	4.20	4.20	4.20	4.20	ksi
$0.4 f'_c =$	2.80	2.80	2.80	2.80	ksi
$f_{Prestress} =$	-0.60	-0.60	-0.60	-0.60	ksi
$f_{DL} =$	2.05	2.05	1.98	1.98	ksi
$f_{SDL} =$	0.14	0.14	0.14	0.14	ksi
$f_{Ped} =$	0.00	0.00	0.00	0.00	ksi
$f_{LL+I} =$	0.27	0.27	0.26	0.26	ksi
<b>RF =</b>	<b>9.64</b>	<b>12.86</b>	<b>10.53</b>	<b>14.04</b>	ksi Full Loading
<b>RF =</b>	<b>7.41</b>	<b>9.88</b>	<b>8.01</b>	<b>10.68</b>	ksi Live + 0.5(pre + D)

**RF<sub>min</sub> = 7.41**

	Interior		Exterior		
	LIVE	L + P	LIVE	L + P	
$6 (f'_c)^{1/2} =$	0.50	0.50	0.50	0.50	ksi
$f_{Prestress} =$	-3.30	-3.30	-3.30	-3.30	ksi
$f_{DL} =$	1.95	1.95	1.87	1.87	ksi
$f_{SDL} =$	0.21	0.21	0.21	0.21	ksi
$f_{Ped} =$	0.00	0.00	0.00	0.00	ksi
$f_{LL+I} =$	0.83	0.83	0.79	0.79	ksi
<b>RF =</b>	<b>1.97</b>	<b>2.62</b>	<b>2.18</b>	<b>2.90</b>	ksi

**RF<sub>min</sub> = 1.97**

**RF<sub>min</sub> = 1.97**  
Inventory = **72.0** Ton

Int. Ext.  
RF = 3.43 3.68 Both are done with Pedestrian Loading  
Operating = **125.5** Ton

Posted = **108.0** Ton

3S2 Truck		
Inventory =	<b>72.0</b>	Tons
Operating =	<b>125.5</b>	Tons
Posted =	<b>108.0</b>	Tons

**Prestressed Girder Ratings - Load Factor Method**

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = MO5

**Material Properties:**

Concrete:

f'c\* = 7000 psi  
f'ci\* = 5500 psi  
f'c = 4000 psi  
Ec\* = 5072 ksi  
Eci\* = 4496 ksi  
Ec = 3834 ksi  
n = 5.52

Prestressing Steel:

f's' = 270 ksi  
E\_s' = 28000 ksi

Reinforcing Steel

f\_y = 60 ksi  
E\_s = 29000 ksi  
n = 7.56

**Girder Geometry and Strand Locations:**

Girder Properties from Conspan:

A = 696 in<sup>2</sup>  
Y<sub>b</sub> = 10.5 in  
I = 34529 in<sup>4</sup>  
d = 21 in  
b<sub>top</sub> = 48 in  
b<sub>eff</sub> = 68 in  
t<sub>s</sub> = 7.5 in  
A<sub>s</sub>midspan = 0.248 in<sup>2</sup>/ft  
Area of Slab Steel / ft

Strands:

# of Strands = 30  
A<sub>s</sub>/strand = 0.217 in<sup>2</sup>  
Y<sub>center</sub> = 3.62 in  
Y<sub>ends</sub> = 3.62 in

Haunch Heights:

Mid Span = 1.00 in  
End = 3.25 in

Prestressing Pattern:

d (in)	Str. @ Center	Str. @ Ends
1.75	14	14
3.75	14	14
5.75	0	0
7.75	0	0
9.75	0	0
11.75	0	0
13.75	0	0
15.75	2	2
20	0	0
22	0	0
24	0	0
26	0	0
28	0	0
30	0	0
32	0	0
34	0	0
Total	30	30

Prestress Loss = 25.90%  
F<sub>i</sub> = 43.9 k  
F<sub>f</sub> = 975.897 k  
e<sub>c</sub> = 6.88 in

**Prestressed Girder Ratings - Load Factor Method**

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = MO5

**Section Properties for Girder Only near Mid Span (For Dead Load):**

# Strands	A (in <sup>2</sup> )	y (in)	Ay (in <sup>3</sup> )	d (in)	I <sub>o</sub> (in <sup>4</sup> )	Ad <sup>2</sup> (in <sup>4</sup> )	I (in <sup>4</sup> )
14	13.732	1.75	24.032	8.47	-	985.36	985.36
14	13.732	3.75	51.497	6.47	-	574.99	574.99
0	0.000	5.75	0.000	4.47	-	0.00	0.00
0	0.000	7.75	0.000	2.47	-	0.00	0.00
0	0.000	9.75	0.000	0.47	-	0.00	0.00
0	0.000	11.75	0.000	1.53	-	0.00	0.00
0	0.000	13.75	0.000	3.53	-	0.00	0.00
2	1.962	15.75	30.898	5.53	-	59.98	59.98
Girder	696	10.5	7308.0	0.28	34529	54.26	34583
P. Steel	29.427		106.4			1620.3	1620
Σ	725.43		7414.4				36204

$Y_b = 10.22$  in  
 $Y_t = 10.78$  in  
 $I = 36204$  in<sup>4</sup>  
 $S_b = 3542.2$  in<sup>3</sup>  
 $S_t = 3358.6$  in<sup>3</sup>

**Section Properties for Girder and Slab near Mid Span:**

$n = 1.32$   
 $n = 5.72$

# Strands	A (in <sup>2</sup> )	y (in)	Ay (in <sup>3</sup> )	d (in)	I <sub>o</sub> (in <sup>4</sup> )	Ad <sup>2</sup> (in <sup>4</sup> )	I (in <sup>4</sup> )
14	13.73	1.75	24.032	14.11	-	2734.329	2734.329
14	13.73	3.75	51.497	12.11	-	2014.154	2014.154
0	0.00	5.75	0.000	10.11	-	0	0
0	0.00	7.75	0.000	8.11	-	0	0
0	0.00	9.75	0.000	6.11	-	0	0
0	0.00	11.75	0.000	4.11	-	0	0
0	0.00	13.75	0.000	2.11	-	0	0
2	1.96	15.75	30.898	0.11	-	0.024069	0.024069
Girder	696.00	10.50	7308.00	5.36	34529.0	20001.5	54530.5
Haunch	36.28	21.50	780.12	5.64	3.02	1153.9	1156.9
Slab Steel	6.63	27.06	179.39	11.20	-	831.5	831.5
Slab	385.52	25.75	9927.24	9.89	1807.14	37703.0	39510.2
P. Steel	29.43	-	106.43	-	-	4748.5	4748.5
Σ	1153.86		18301.2				100778

$Y_b = 15.86$  in  
 $Y_t = 5.14$  in  
 $Y_{t\text{slab}} = 13.64$  in  
 $I = 100778$  in<sup>4</sup>  
 $S_b' = 6353.9$  in<sup>3</sup>  
 $S_t' = 19609.5$  in<sup>3</sup>

**Prestressed Girder Ratings - Load Factor Method**

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = MO5

**Section Properties for Girder and Slab near Mid Span:(Creep Considered - 3n)**

n = 1.32 concrete  
n = 5.72 steel

# Strands	A (in <sup>2</sup> )	y (in)	Ay (in <sup>3</sup> )	d (in)	I <sub>o</sub> (in <sup>4</sup> )	Ad <sup>2</sup> (in <sup>4</sup> )	I (in <sup>4</sup> )
14	13.73	1.75	24.032	11.04	-	1674.305	1674.305
14	13.73	3.75	51.497	9.04	-	1122.706	1122.706
0	0.00	5.75	0.000	7.04	-	0	0
0	0.00	7.75	0.000	5.04	-	0	0
0	0.00	9.75	0.000	3.04	-	0	0
0	0.00	11.75	0.000	1.04	-	0	0
0	0.00	13.75	0.000	0.96	-	0	0
2	1.96	15.75	30.898	2.96	-	17.16669	17.16669
Girder	696.00	10.50	7308.00	2.29	34529.0	3655.9	38184.9
Haunch	12.09	21.50	260.04	8.71	1.01	917.2	918.2
Slab Steel	6.63	27.06	179.39	14.27	-	1349.6	1349.6
Slab	128.51	25.75	3309.08	12.96	602.38	21578.2	22180.6
P. Steel	29.43	-	106.43	-	-	2814.2	2814.2
Σ	872.66		11162.9				65447

Y<sub>b</sub> = 12.79 in  
Y<sub>t</sub> = 8.21 in  
Y<sub>tslab</sub> = 16.71 in  
I = 65447 in<sup>4</sup>  
S<sub>b</sub>" = 5116.3 in<sup>3</sup>  
S<sub>t</sub>" = 7973.5 in<sup>3</sup>

**Ultimate Strength Analysis:**

d = 25.88 in  
ρ\* = 0.00370  
β<sub>1</sub> = 0.7  
f<sub>su</sub>\* = 231.55 ksi      f'<sub>c</sub> = 4 ksi  
φ M<sub>n</sub> = 2833.69 k-ft      Impact = 0.278

	Interior	Exterior		Trk Wt = 36.64 Ton
M <sub>DL</sub> =	574.5	553.1	k-ft	M <sub>LL+I</sub> = 779.4 k-ft
M <sub>SDL</sub> =	90.8	90.8	k-ft	M <sub>LL+I</sub> per Consys * Impact
M <sub>LL+I</sub> =	520	490	k-ft	Interior
M <sub>PED</sub> =	0	0	k-ft	DF = 0.6666
RF(w/o Ped) =	1.75	1.88		Mped = 0
RF(w/ Ped) =	2.33	2.51		Exterior
RF <sub>min</sub> =	1.75			k-ft

Distribution Factors are Per Truck per AASHTO 3.23.2.3.2

**Prestressed Girder Ratings - Load Factor Method**

MODOT Bridge Inspection Rating Manual - Section 4

Truck Type = MO5

	Interior		Exterior		
	LIVE	L + Ped	LIVE	L + Ped	
$0.6 f'_c =$	4.20	4.20	4.20	4.20	ksi
$0.4 f'_c =$	2.80	2.80	2.80	2.80	ksi
$f_{\text{Prestress}} =$	-0.60	-0.60	-0.60	-0.60	ksi
$f_{\text{DL}} =$	2.05	2.05	1.98	1.98	ksi
$f_{\text{SDL}} =$	0.14	0.14	0.14	0.14	ksi
$f_{\text{Ped}} =$	0.00	0.00	0.00	0.00	ksi
$f_{\text{LL+I}} =$	0.32	0.32	0.30	0.30	ksi
<b>RF =</b>	<b>8.20</b>	<b>10.94</b>	<b>8.96</b>	<b>11.94</b>	ksi Full Loading
<b>RF =</b>	<b>6.30</b>	<b>8.40</b>	<b>6.81</b>	<b>9.08</b>	ksi Live + 0.5(pre + D)

**RF<sub>min</sub> = 6.30**

	Interior		Exterior		
	LIVE	L + P	LIVE	L + P	
$6 (f'_c)^{1/2} =$	0.50	0.50	0.50	0.50	ksi
$f_{\text{Prestress}} =$	-3.30	-3.30	-3.30	-3.30	ksi
$f_{\text{DL}} =$	1.95	1.95	1.87	1.87	ksi
$f_{\text{SDL}} =$	0.21	0.21	0.21	0.21	ksi
$f_{\text{Ped}} =$	0.00	0.00	0.00	0.00	ksi
$f_{\text{LL+I}} =$	0.98	0.98	0.93	0.93	ksi
<b>RF =</b>	<b>1.67</b>	<b>2.23</b>	<b>1.85</b>	<b>2.47</b>	ksi

**RF<sub>min</sub> = 1.67**

**RF<sub>min</sub> = 1.67**  
Inventory = **61.3** Ton

Int. Ext.  
RF = 2.91 3.13 Both are done with Pedestrian Loading  
Operating = **106.8** Ton

Posted = **91.8** Ton

MO5 Truck		
Inventory =	<b>61.3</b>	Tons
Operating =	<b>106.8</b>	Tons
Posted =	<b>91.8</b>	Tons

**Prestressed Girder Ratings - Load Factor Method - Summary**  
*MODOT Bridge Inspection Rating Manual - Section 4*

**HS20 Truck:**

Inventory Rating =	51.7	Tons	>	36	Tons	<b>OKAY</b>
Operating Rating =	90.1	Tons				
Posting =	77.5	Tons	>	40	Tons	<b>No Posting Req'd</b>

---

**H20 Truck:**

Inventory Rating =	41.3	Tons	>	20	Tons	<b>OKAY</b>
Operating Rating =	72.0	Tons				
Posting =	61.9	Tons	>	23	Tons	<b>No Posting Req'd</b>

---


**3S2 Truck:**

Inventory Rating =	72.0	Tons	>	36.64	Tons	<b>OKAY</b>
Operating Rating =	125.5	Tons				
Posting =	108.0	Tons	>	40	Tons	<b>No Posting Req'd</b>

---

**MO5 Truck:** *(Commercial Zones Only)*

Inventory Rating =	61.3	Tons	>	36.64	Tons	<b>OKAY</b>
Operating Rating =	106.8	Tons				
Posting =	91.8	Tons	>	70	Tons	<b>No Posting Req'd</b>




3.31.2011



4-7-2011

DATE PREPARED		3/21/2011	
ROUTE	STATE	MO	
DISTRICT	SHEET NO.	1	
CITY			
FENTON			
JOB NO.			
1100110			
FED.-AID PROJECT NO.			
BRM-4989(606)			
PROJECT NO.			
N/A			
BRIDGE NO.			
1420013			



Note:  
Roadway fill shall be completed to the final roadway section and up to the elevation of the bottom of the concrete beam within the limits of the structure and for not less than 25 feet in back of the fill face of the end bents before any piles are driven for any bents falling within the embankment section.


City of Fenton  
Indicates location of borings.  
Notice and Disclaimer Regarding Boring Log Data

The locations of all subsurface borings for this structure are shown on the bridge plan sheet for this structure. Boring data for the numbered locations is shown on Sheet No. B-17 of the original design plans. The boring data for all locations indicated, as well as any other boring logs or other factually records of subsurface data and investigations performed by the department for the design of the project, is available from the Project Contract upon written request. No greater significance or weight should be given to the boring data depicted on the plan sheets than is subsurface data available from the district or elsewhere.

The City does not represent or warrant that any such boring data accurately depicts the conditions to be encountered in constructing this project. A contractor assumes all risks it may encounter in basing its bid prices, time or schedule of performance on the boring data depicted here or those available from the district, or on any other documentation not expressly warranted, which the contractor may obtain from the City.

For General Notes, Foundation Data, Hydrologic Data, Location Sketch, and Estimated Quantities see Sheet No. 2.

Site Benchmark:  
18-36 427.00 - "Standard Tablet" stamped 75-75 S.L.C. set in southeast end of north abutment of old bridge over Meramec River along Gravois Road.



NOTE: DRAWINGS ARE NOT TO SCALE, FOLLOW DIMENSIONS

**HORNER & SHIFRIN, INC.**  
ENGINEERS  
5200 DARLAND AVE., ST. LOUIS, MO 63110-1490  
314-531-4321 FAX: 314-531-6566 www.HornerShifrin.com  
Discipline: Professional Engineering  
Certification of Authority: 000159  
Expiration Date: December 31, 2012

OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK

GENERAL PLAN AND ELEVATION

Designed: TPL  
Detailed: CAB  
Checked: TPL



4-7-2011

DATE PREPARED 3/21/2011	
ROUTE	STATE MO
DISTRICT	SHEET NO. 2
CITY FENTON	
JOB NO. 1100110	
FED.-AID PROJECT NO. BRM-4989(606)	
PROJECT NO. N/A	
BRIDGE NO. 1420013	

Item	Substr.	Superstr.	Total
Class 1 Excavation	cu. yard	640	640
Class 1 Excavation in Rock	cu. yard	10	10
Class 2 Excavation	cu. yard	101	101
Class 2 Excavation in Rock	cu. yard	19	19
Removal of Bridges	lump sum	-	1
Bridge Approach Slab (Bridge)	sq. yard	267	267
66" Precast Concrete Pipe, Storm Sewer Adjustment	lump sum	-	1
Structural Steel Piles (12 in.)	linear foot	120	120
Pile Point Reinforcement	each	6	6
Class B Concrete (Substructure)	cu. yard	252.1	252.1
Slab on Prestressed Concrete Box Beam	sq. yard	-	308
Prestressed Concrete Box Beam (21")	linear foot	-	390
Reinforcing Steel (Bridges)	pound	18,380	18,380
Reinforcing Steel (Epoxy Coated)	pound	1,410	1,410
Bridge Guardrail	linear foot	-	117
Plain Neoprene Bearing Pad	each	-	14
Vertical Drain at End Bents	each	-	2

**GENERAL NOTES:**

Design Specifications:  
 2002 - AASHTO 17th Edition  
 Load Factor Design  
 Seismic Performance Category B  
 Acceleration Coefficient = 0.11

Design Loading:  
 HS20 Modified  
 35#/sq. Ft. Future Wearing Surface  
 Lateral Earth Pressure -  $P_h = 55h + 0.45q$   
 where:  $P_h$  = lateral earth pressure per foot of wall, psf  
 $h$  = depth below grade at wall, ft.  
 $q$  = surcharge load, psf  
 Vertical Earth Pressure = 120 pcf  
 Superstructure: Simply-supported, non-composite for dead load,  
 Composite for live load.

Reference:  
 All construction shall be in accordance with the current editions of the Missouri Standard Specifications for Highway Construction and Missouri Bridge Standard Drawings.

Design Unit Stresses:  
 Class B Concrete (Substructure)  $f'c = 3,000$  psi  
 Class B-2 Concrete (Superstructure, except Prestressed Box Beams)  $f'c = 4,000$  psi  
 Reinforcing Steel (Grade 60)  $f_y = 60,000$  psi  
 Steel Pile (ASTM A709 Grade 36)  $f_b = 9,000$  psi  $f_y = 36,000$  psi  
 Anchor Rods (ASTM F1554 Grade 36)  $f_y = 36,000$  psi  
 For precast prestressed panel stresses, see Sheet No. 14.  
 For prestressed box beam stresses, see Sheet No. 13.

Neoprene Pads:  
 Plain Neoprene Bearing Pads shall be in accordance with Sec 716.  
 Bearings shall be 60 diameter neoprene pads.

Joint Filler:  
 All joint filler shall be in accordance with Sec 1057 for preformed sponge rubber expansion and partition joint filler, except as noted.


Reinforcing Steel:  
 Minimum clearance to reinforcing steel shall be  $1\frac{1}{2}$ ", unless otherwise shown.

Protective Coat:  
 Protective Coating: System H in accordance with Sec 1081.

Hydrologic Data Table:  
 See original design plans for this bridge, included as an information sheet at the end of these plans, for Hydrologic Data.

Backfill:  
 The backfill at End Bent No. 1 shall be granular to match the assumed design loading.

Miscellaneous:  
 "Sec" refers to the sections in the standard and supplemental specifications unless specified otherwise.



STEEL PILE SPLICE

All concrete above the construction joint in the end bents is included in the Estimated Quantities for Slab on Prestressed Concrete Box Beam.

All reinforcement in End Bent No. 2 is included in the Estimated Quantities for Slab on Prestressed Concrete Box Beam.

Cost of channel shear connectors C4 x 5.4 (ASTM A709 Grade 36) in place will be considered completely covered by the contract unit price for Structural Steel Piles (12 in.).

The Estimated Quantities for Slab on Concrete Box Beam are based on skewed precast prestressed end panels.

Item	cu. yard	Total
Class B-2 Concrete	81.2	
Reinforcing Steel		2,900
Reinforcing Steel (Epoxy Coated)		9,650

The table of Estimated Quantities for Slab on Prestressed Concrete Box Beam represents the quantities used by the State in preparing the cost estimate for concrete slabs. The area of the concrete slab will be measured to the nearest square yard with the horizontal dimensions as shown on the plan of slab. Payment for prestressed panels, conventional forms, all concrete and coated and uncoated reinforcing steel will be considered completely covered by the contract unit price for the slab. Variations may be encountered in the estimated quantities but the variations cannot be used for an adjustment in the contract unit price.

Method of forming the slabs shall be as shown on the plans and in accordance with Sec 703. All hardware for forming the slab to be left in place as a permanent part of the structure shall be coated in accordance with ASTM A123 or ASTM B633 with a thickness class SC 4 and a finish type I, II or III.

Class B-2 Concrete quantity is based on minimum top flange thickness and minimum joint material thickness.

The prestressed panel quantities are not included in the table of Estimated Quantities for Slab on Prestressed Concrete Box Beam.


Bent No.		1	2	
Driven Pile	Type	-	Foundation	
	Pile Type and Size	-	HP12x53	
	Number	-	6	
	Approximate Length	foot	-	20
	Pile Driving Verification Method	-	-	Modified Gates Formula
Spread Footing	Design Bearing	kip	-	129
	Hammer Energy Required	foot-pound	-	14,500
Foundation Material	Design Bearing	ksf	9.1	-

Manufactured pile point reinforcement shall be used on all piles in this structure.

Drainage Area	= 4.32 sq. miles (Rolling)
Design Discharge	= 4,050 cu. ft./second (100 years)
Design H.W. Elevation	= 420.55 feet (100 years)
Estimated Backwater	= 9.5 feet *

\* Controlled by backwater from Meramec River

The Hydrologic Data Table is taken from Drawing B-2 of the original design plans and is included here for information only.



LOCATION SKETCH

NOTE: DRAWINGS ARE NOT TO SCALE. FOLLOW DIMENSIONS

**HORNER & SHIFRIN, INC.**  
**ENGINEERS**  
 5200 OAKLAND AVE., ST. LOUIS, MO 63110-1450  
 314-551-4321 FAX: 314-551-6966 www.horner-shifrin.com  
 Equal Opportunity Employer M/F/V  
 License No. 0001519  
 Expiration Date: December 31, 2012

ESTIMATED QUANTITIES, FOUNDATION DATA, AND GENERAL NOTES

Designed: TPL  
 Detailed: CAB  
 Checked: KLH

**GENERAL NOTES, ESTIMATED QUANTITIES, AND PILE DATA**



4-7-2011

DATE PREPARED  
3/21/2011

ROUTE STATE  
MO

DISTRICT SHEET NO.  
3

CITY  
FENTON

JOB NO.  
1100110

FED.-AID PROJECT NO.  
BRM-4989(606)

PROJECT NO.  
N/A

BRIDGE NO.  
1420013

DATE	DESCRIPTION
3/28/11	Revised Beam Elevations
4/05/11	Revised Note


**HORNER & SHIFFIN, INC.**  
ENGINEERS

5600 DAKLAND AVE., ST. LOUIS, MO 63110-1490  
314-531-6321 FAX: 314-531-6966 www.hornerShiffin.com  
Discipline: Professional Engineering  
Certification number: 000232  
Expiration Date: December 31, 2012

NOTE: DRAWINGS ARE NOT TO SCALE. FOLLOW DIMENSIONS




OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK

DETAILS OF END BENT NO. 1  
SHEET 1 OF 5



**DEVELOPED SECTION NEAR END BENT**  
Note: Footing shall be keyed 6" (min.) into sound rock.  
Footing Elevation may differ from that shown.  
See Sheet No. 5 for vertical wall reinforcement.

66" RCP shall be adjusted as specified for construction of the bridge. All costs associated with the RCP adjustment shall be considered completely covered by the contract unit price for 66" Precast Concrete Pipe, Storm Sewer Adjustment.



PLAN OF BEAM SHOWING DIMENSIONS  
DETAILS OF END BENT NO. 1

Designed: TPL  
Detailed: CAB  
Checked: KLH




3.28.2011

DATE PREPARED 3/21/2011	
ROUTE	STATE MO
DISTRICT	SHEET NO. 4
CITY FENTON	
JOB NO. 1100110	
FED.-AID PROJECT NO. BRM-4989(606)	
PROJECT NO. N/A	
BRIDGE NO. 1420013	


DATE	DESCRIPTION
3/28/11	Revised Beam Elevations

**HORNER & SHIRIN, INC.**  
ENGINEERS  
5200 DAKLAND AVE., ST. LOUIS, MO 63110-1490  
314-531-4321 FAX: 314-531-6966 www.HornerShirin.com  
Discipline: Professional Engineering  
Certificate of Authority: 000159  
Expiration Date: December 31, 2012


NOTE: DRAWINGS ARE NOT TO SCALE. FOLLOW DIMENSIONS  
OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK  
DETAILS OF END BENT NO. 1  
SHEET 2 OF 5



PART PLAN  
(Wing walls not shown)




PART PLAN




PART ELEVATION


END REINFORCEMENT DETAIL



PART SECTION A-A



PART SECTION B-B



DETAIL "A"

Notes:  
Place U4, U5, U6, U7, H20 and V1 bars parallel to centerline of roadway.

DETAILS OF END BENT NO. 1 DIAPHRAGM

Designed: TPL  
Detailed: CAB/KLH/MAB  
Checked: TPL



4-7-2011

DATE PREPARED  
3/21/2011

ROUTE STATE  
MO

DISTRICT SHEET NO.  
5

CITY  
FENTON

JOB NO.  
1100110

FED.-AID PROJECT NO.  
BRM-4989(606)

PROJECT NO.  
N/A

BRIDGE NO.  
1420013


DATE	DESCRIPTION
4/05/11	Revised Details

**HORNER & SHIFRIN, INC.**  
ENGINEERS  
5200 DAKLAND AVE., ST. LOUIS, MO 63110-1490  
314-531-4321 FAX: 314-531-6966 www.horner-shifrin.com  
Professional Engineer License No. 100069  
Expiration Date: December 31, 2012

NOTE: DRAWINGS ARE NOT TO SCALE, FOLLOW DIMENSIONS


OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK

DETAILS OF END BENT NO. 1  
SHEET 3 OF 5



### PLAN OF BEAM SHOWING REINFORCEMENT

Note A: 15-#4-F103 @ 12" (See Section A-A for bar placement)  
\* 3 Spa. @ 12"



### ANCHOR ROD DETAIL

Notes:  
Hole (2"  $\varnothing$ ) to be grouted with expansive type mortar meeting the requirements of Section 1066 of Standard Specifications.  
The cost of the anchor rods, complete-in-place, shall be considered completely covered by the contract unit price of other items.


Notes:  
Place U4, U5, U6, U7, H10 and V1 bars parallel to centerline of roadway.  
Field cut or bend F-bars as required to fit.

### DETAILS OF END BENT NO. 1

Designed: TPL  
Detailed: CAB/KLH/MAB  
Checked: TPL




4-7-2011  
 DATE PREPARED  
 3/21/2011  
 ROUTE STATE  
 DISTRICT SHEET NO.  
 6  
 CITY  
 FENTON  
 JOB NO.  
 1100110  
 FED.-AID PROJECT NO.  
 BRM-49891606  
 PROJECT NO.  
 N/A  
 BRIDGE NO.  
 1420013




SECTION A-A DIMENSIONS AT BRIDGE  
 Section B-B similar

SECTION A-A REINFORCEMENT AT BRIDGE  
 Section B-B similar




SECTION C-C DIMENSIONS AT WING WALL  
 Section D-D similar




SECTION C-C REINFORCEMENT AT WING WALL  
 Section D-D similar

Note: Finished groundline in front of wall shall be the same elevation as existing conditions.



EXPANSION JOINT DETAIL



CONTRACTION JOINT DETAIL

Note: Backfill shall be a granular material.

DATE	DESCRIPTION
4/05/11	Revised Notes

NOTE: DRAWINGS ARE NOT TO SCALE. FOLLOW DIMENSIONS

**HORNER & SHIFRIN, INC.**  
 ENGINEERS  
 5200 OAKLAND AVE., ST. LOUIS, MO 63110-1490  
 314-531-4321 FAX: 314-531-6966 www.hornerShifrin.com  
 01 Licenses: Professional Engineering License No. 15199  
 Expiration Date: December 31, 2012

OLD HIGHWAY 141  
 BRIDGE OVER  
 FENTON CREEK

DETAILS OF END BENT NO. 1  
 SHEET 4 OF 5

Designed: TPL  
 Detailed: KLH  
 Checked: KLH

DETAILS OF END BENT NO. 1




4-7-2011

DATE PREPARED  
3/21/2011  
ROUTE STATE  
DISTRICT SHEET NO.  
7  
CITY  
FENTON  
JOB NO.  
1100110  
FED.-AID PROJECT NO.  
BRM-49891606  
PROJECT NO.  
N/A  
BRIDGE NO.  
1420013

DATE	DESCRIPTION
4/05/11	Revised Quantities


**HORNER & SHIFRIN, INC.**  
ENGINEERS  
5320 OAKLAND AVE. ST. LOUIS, MO 63110-1480  
314-531-0331 FAX: 314-531-5961 www.horner-shifrin.com  
Discipline: Professional Engineering  
Certificate of Authority: 000159  
Expiration Date: December 31, 2012

OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK  
DETAILS OF END BENT NO. 1  
SHEET 5 OF 5




PART ELEVATION OF EXTERIOR WALL  
SHOWING BLOCK-OUT FOR 66" RCP

NOTE:  
Cut plan reinforcing bars  
to clear pipe block-out.




SECTION A-A  
(Plan bars not shown)




DETAIL "A"  
(Keyed Joint)

NOTE:  
Place  $\frac{5}{16}$ " joint filler around reinforced  
concrete pipe at block-out.

The block-out may be eliminated at  
contractors election. If block-out is  
eliminated, reinforcement shall be as  
shown except plan reinforcement may be  
bent to clear pipe.



PART ELEVATION SHOWING END BENT  
NO. 1 NORTH WING TIP  
(See other sheets for reinforcement  
in rest of wing wall.)



FOOTING PLAN OF NORTH WING  
SHOWING REINFORCEMENT  
Field cut or bent F-bars as required to fit.


Item	Quantity
Class 1 Excavation	cu. yard 595
Class 1 Excavation in Rock	cu. yard 10
Class 2 Excavation	cu. yard 101
Class 2 Excavation in Rock	cu. yard 19
Class B Concrete (Substructure)	cu. yard 231.7
Reinforcing Steel (Bridges)	lbs. 18,380
Reinforcing Steel (Epoxy Coated)	lbs. 1,410
	18,140

Note: These quantities are included in the estimated  
quantities table on Sheet No. 2.





NOTE: DRAWINGS ARE NOT TO SCALE. FOLLOW DIMENSIONS

DETAILS OF END BENT NO. 1

Designed: TPL  
Detailed: CAB/MAB  
Checked: TPL



DATE PREPARED	
3/21/2011	
ROUTE	STATE
	MO
DISTRICT	SHEET NO.
	8
CITY	
FENTON	
JOB NO.	
1100110	
FED.-AID PROJECT NO.	
BRM-4989(606)	
PROJECT NO.	
N/A	
BRIDGE NO.	
1420013	



**OPTIONAL BENT DRAIN (\*)**

(\*) Only if rock is encountered at outside of wing.

**Note:**  
 Drain pipe may be either 6" diameter corrugated metallic-coated steel pipe underdrain, 4" diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4" diameter corrugated polyethylene (PE) drain pipe.

Place drain pipe at fill face of end bent and slope to lowest grade of ground line, also missing the lower beam of end bent by 1 1/2". (See elevation at end bent.)

Perforated pipe shall be placed at fill face side at the bottom of end bent and plain pipe shall be used where the vertical drain ends to the exit at ground line.

Vertical drain at End Bent 1 shall daylight to the North.

Vertical drain core shall extend to bottom of walls at End Bent 1.

Vertical drain core shall extend to the ends of wing walls at both end bents, except may be omitted for the short section of North wing at End Bent No. 1.

NOTE: DRAWINGS ARE NOT TO SCALE. FOLLOW DIMENSIONS

**HORNER & SHIFRIN, INC.**  
**ENGINEERS**  
 5200 OAKLAND AVE., ST. LOUIS, MO 63110-1490  
 314-531-4321 FAX: 314-531-6966 www.HornerShifrin.com  
 Disciplines: Professional Engineering  
 Certificate of Authority: 000159  
 Expiration Date: December 31, 2012

OLD HIGHWAY 141  
 BRIDGE OVER  
 FENTON CREEK  
 - VERTICAL DRAIN DETAILS

Designed: TPL  
 Detailed: KLH  
 Checked: KLH



4-7-2011

DATE PREPARED  
3/21/2011

ROUTE STATE  
MO  
DISTRICT SHEET NO.  
9

CITY  
FENTON

JOB NO.  
1100110

FED.-AID PROJECT NO.  
BRM-49891(606)


PROJECT NO.  
N/A

BRIDGE NO.  
1420013


DATE	DESCRIPTION
4/05/11	Revised Notes

**HORNER & SHIFRIN, INC.**  
ENGINEERS  
5200 OAKLAND AVE. ST. LOUIS, MO 63110-1490  
314-531-4221 FAX: 314-531-6866 www.HornerShifrin.com  
Professional Engineer License No. 00000000  
Expiration Date: December 31, 2012


NOTE: DRAWINGS ARE NOT TO SCALE. FOLLOW DIMENSIONS  
OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK  
DETAILS OF END BENT 2  
SHEET 1 of 3




TYPICAL SECTION THRU KEY



PLAN OF BEAM SHOWING DIMENSIONS



ANCHOR ROD DETAIL  
Notes:  
Hole (2" Ø) to be grouted with expansive type mortar meeting the requirements of Section 1066 of Standard Specifications.  
The cost of the anchor rod, complete in-place, shall be considered completely covered by the contract unit price of other items.



PLAN OF BEAM SHOWING REINFORCEMENT

\* 3 spaces @ 6"  
\*\* 2 spaces @ 6"  
Notes:  
Place U21, U22, U23, U24, U25, U26, U27, H30 and V21 bars parallel to centerline of roadway.  
[Cut or bend U1 and V1 bars to fit.]  
△ Cut or bend U21 and V21 bars to fit.

DETAILS OF END BENT NO. 2

Designed: TPL  
Detailed: CAB  
Checked: KLH







4-7-2011

DATE PREPARED	3/21/2011
ROUTE	STATE
DISTRICT	SHEET NO.
CITY	10
JOB NO.	FENTON
FED.-AID PROJECT NO.	1100110
PROJECT NO.	BRM-4989(606)
BRIDGE NO.	N/A
	1420013

DATE	DESCRIPTION
3/28/11	Revised Beam Elevations
4/05/11	Added Pile Detail

**HORNER & SHIFRIN, INC.**  
**ENGINEERS**  
 5200 CARLAND AVE., ST. LOUIS, MO 63110-1490  
 314-531-4321 FAX: 314-531-8966 www.hornerShifrin.com  
 Description: Professional Engineering  
 Expiration Date: December 31, 2012

OLD HIGHWAY 141  
 BRIDGE OVER  
 FENTON CREEK  
 DETAILS OF END BENT 2  
 SHEET 2 OF 3



PART PLAN  
 DETAILS OF END BENT NO. 2


Designed: TPL  
 Detailed: CAB  
 Checked: KLH

NOTE: DRAWINGS ARE NOT TO SCALE. FOLLOW DIMENSIONS




4-7-2011


DATE PREPARED 3/21/2011	
ROUTE	STATE MO
DISTRICT	SHEET NO. 11
CITY FENTON	
JOB NO. 1100110	
FED.-AID PROJECT NO. BRM-49891(606)	
PROJECT NO. N/A	
BRIDGE NO. 1420013	




ELEVATION E-E




ELEVATION F-F




DETAIL "A"




SECTION A-A




SECTION B-B



SECTION C-C



SECTION D-D



TYPICAL SECTION THRU WING

\* Placed with grade

Item	Quantity
Class 1 Excavation	cu. yard 45
Structural Steel Piles (12 in.)	linear foot 120
Pile Point Reinforcement	each 6
Class B Concrete (Substructure)	cu. yard 20.4

Note: These quantities are included in the estimated quantities table on Sheet No. 2.


DETAILS OF END BENT NO. 2

Designed: TPL  
Detailed: CAB  
Checked: KLH


NOTE: DRAWINGS ARE NOT TO SCALE, FOLLOW DIMENSIONS

**HORNER & SHIFRIN, INC.**  
ENGINEERS  
5200 W. LAMAR ST., SUITE 100, ST. LOUIS, MO 63110-1480  
314-431-4321 FAX: 314-431-4966 www.horner-shifrin.com  
Disseminated Professional Engineering  
Certificate of Authority: 000159  
Expiration Date: December 31, 2012


OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK  
DETAILS OF END BENT 2  
SHEET 3 OF 3




SECTION A-A




SECTION B-B  
(Showing dimensions)



VIEW C-C



PLAN VIEW



SECTION B-B  
(Showing reinforcement and strand locations)

\* Debond strand for 16 feet from end of beam. Prestressing strands shall be cut flush with the box beam unit ends.

MINIMUM BAR LAP

- #4 bar = 2'-0"
- #5 bar = 2'-6"

BAR LIST  
ONE BEAM ONLY

(For Information Only)

Bar	No.	Size	Length	Shape
A(E)	16	#4	3'-7"	—
A1(E)	34	#4	3'-10"	—
B(E)	5	#5	55'-5"	—
B1(E)	4	#4	55'-5"	—
S(E)	78	#4	7'-5"	—
S1(E)	10	#4	5'-11"	—
S2(E)	68	#4	6'-2"	—
S3(E)	156	#4	3'-0"	—
U(E)	12	#5	4'-0"	—
U1(E)	4	#4	6'-0"	—

NOTE:  
See Sheet 13 for additional details and Bill of Material.

Place the number of strands specified in each row symmetrically about the centerline of beam in the permissible strand locations shown.

Finish the top surface of deck beams in accordance with Sec. 1029 for Surface Finish, I-Girders.



3-21-2011

DATE PREPARED: 3/21/2011  
ROUTE: STATE  
DISTRICT: MO  
SHEET NO.: 12

CITY: FENTON  
JOB NO.: 1100110

FED.-AID PROJECT NO.: BRM-4989(606)

PROJECT NO.: N/A

BRIDGE NO.: 1420013

DATE	DESCRIPTION



5200 OAKLAND AVE. ST. LOUIS, MO 63110-1490  
314-531-4321 FAX: 314-531-4966 www.horner-shifrin.com  
Discipline: Professional Engineering  
Certificate of Authority: 000159  
Expiration Date: December 31, 2012

NOTE: DRAWINGS ARE NOT TO SCALE. FOLLOW DIMENSIONS

OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK  
DETAILS OF PRECAST  
PRESTRESSED 48" BOX BEAMS  
SHEET 1 OF 2

Designed: TPL  
Detailed: CAB  
Checked: KLH

DETAILS OF PRECAST PRESTRESSED 48" BOX BEAMS



4-7-2011

DATE PREPARED 3/21/2011	
ROUTE	STATE MO
DISTRICT	SHEET NO. 13
CITY FENTON	
JOB NO. 1100110	
FED.-AID PROJECT NO. BRM-49891(606)	
PROJECT NO. N/A	
BRIDGE NO. 1420013	

DATE	DESCRIPTION
4/05/11	Revised Girder Details


**HORNER & SHIFRIN, INC.**  
ENGINEERS

5200 DUKELAND AVE., ST. LOUIS, MO 63110-4480  
314-531-1100  
Disposal: Professional Engineer, Inc.  
Certification of Authority: 000159  
Expiration Date: December 31, 2012


OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK

DETAILS OF PRECAST  
PRESTRESSED 48" BOX BEAMS  
SHEET 2 OF 2


NOTE: DRAWINGS ARE NOT TO SCALE, FOLLOW DIMENSIONS




PLAN VIEW




SECTION SHOWING VENT HOLE




BAR S(E)




BAR S2(E)




BAR A1(E)




BAR S1(E)




BAR S3(E)



BAR U(E)



BAR U1(E)



LIFTING LOOP DETAIL

- NOTES:
- Concrete for prestressed girders shall be Class A-1 with  $f'c = 7,000$  psi and  $f'ci = 5,500$  psi.
  - (+) indicates prestressing strand.
  - Use 30 strands with an initial prestress force of 1318 kips.
  - Prestressing tendons shall be uncoated, seven-wire, low-relaxation strands, 0.6 inch diameter in accordance with AASHTO M 203, Grade 270. Pretensioned members shall be in accordance with Sec 1029.
  - \*\*\* At contractor's option a 1 1/2" to 1 3/4" smooth finish strip is permitted to facilitate placement of preformed fiber expansion joint material or expanded or extruded polystyrene bedding material for the prestressed panels.
  - All dimensions are out to out.
  - Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.
  - Actual lengths are measured along centerline of bar to the nearest inch.
  - All reinforcement shall be grade 60.
  - All bars shall be epoxy coated.

DETAILS OF PRECAST PRESTRESSED 48" BOX BEAMS

Designed: TPL  
Detailed: CAB  
Checked: K LH



3-21-2011

DATE PREPARED 3/21/2011	
ROUTE	STATE MO
DISTRICT	SHEET NO. 14
CITY FENTON	
JOB NO. 1100110	
FED.-AID PROJECT NO. BRM-4989(606)	
PROJECT NO. N/A	
BRIDGE NO. 1420013	

DESCRIPTION	DATE


**HORNER & SHIFRIN, INC.**  
ENGINEERS

5200 OAKLAND AVE., ST. LOUIS, MO 63110-1490  
314-531-4321 FAX: 314-531-6966 www.horner-shifrin.com  
Discipline: Professional Engineering  
Certificate of Authority: 000159  
Expiration Date: December 31, 2012


NOTE: DRAWINGS ARE NOT TO SCALE. FOLLOW DIMENSIONS

OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK


DETAILS OF PRECAST  
PRESTRESSED PANELS




PLAN OF PRECAST PRESTRESSED PANELS PLACEMENT




PLAN OF PRECAST PRESTRESSED PANEL



DETAIL "A"



SECTION A-A



SECTION B-B

Note: Use camber and dead load deflection data on Sheet No. 15 for determining thickness of preformed fiber expansion joint material or polystyrene bedding material within the limits noted in general notes.

**NOTES:**  
Welded wire fabric or welded deformed bar mats providing a minimum area of reinforcing perpendicular to strands of 0.22 sq. in./ft., with spacing parallel to strands sufficient to insure proper handling, may be used in lieu of the top #3-P2 bars shown. Wire or bar diameter shall not be larger than 0.375 inches. The above alternative reinforcement criteria may be used in lieu of the #3-P3 bars, when required, and placed over a width not less than 2 feet.  
The reinforcing steel shall be tied securely to the 3/8" Ø strands with the following maximum spacing in each direction:  
#3-P2 bars at 16 inches.  
Welded wire fabric or welded deformed bar mats at 2'-0".

Tie the #3-U1 bars to the #3-P2 bars, to the welded wire fabric or the welded deformed bar mats at about 3'-0" centers.

All reinforcement other than prestressing strands shall be epoxy coated.

Precast panels may be in contact with stirrup reinforcing in diaphragms.

Cost of S-bars will be considered completely covered by the contract unit price for the slab.

S-bars are not listed in the bill of reinforcing.

(1) End panels shall be dimensioned 1" min. to 1 1/2" max. from the inside face of diaphragm.

(2) S-bars shown are bottom steel in slab between panels and used with squared end panels only.

(3) Extend S-bars 18 inches beyond the front face of end bents only.


(4) In order to maintain minimum slab thickness, it may be necessary to raise the grade uniformly throughout the structure. No payment will be made for additional labor or materials required for necessary grade adjustment.

(5) Any strand 2'-0" or shorter shall have a #4 reinforcing bar on each side of it, centered between strands. Strands 2'-0" or shorter may then be deboned at the fabricator's option.


(6) All panel support pads shall be glued to the girder. When support thickness exceeds 1 1/2 inches, the pads shall be glued top and bottom. The glue used shall be the type recommended by the panel support pads manufacturer.

(7) Use #3-P3 bars if panel is skewed 45° or greater.


(8) Minimum reinforcement steel length shall be 2'-0".



SECTION C-C




BENDING DIAGRAM FOR U1 BAR  
(U1 Bars may be oriented at right angles to location and spacing shown. U1 Bars shall be placed between P1 bars).




PLAN OF PRECAST PRESTRESSED PANEL (SKEWED END-OPTIONAL)

Designed: TPL  
Detailed: CAB  
Checked: KLH

DETAILS OF PRECAST PRESTRESSED PANELS



PLAN OF SLAB SHOWING REINFORCEMENT



**BEAM CAMBER DIAGRAM**

	Span (1-2)	
	"A"	"B"
Ext. beam	1 1/16"	2 1/16"
Int. beam	1 5/16"	2 1/16"

	Span (1-2)	
	"A"	"B"
Ext. beam	2 1/4"	3 3/8"
Int. beam	2 1/8"	3 3/8"


Revised

Notes:


Conversion factors for girder camber  
0.25 pt. = 0.7125 x 0.5 pt.

If girder camber is different from that shown in the camber diagram, adjustment of the slab haunches, an increase in slab thickness or a raise in grade uniformly throughout the structure shall be necessary. No payment will be made for additional labor or materials required for variation in haunching, slab thickness or grade adjustment.

Concrete in the slab haunches is included in the Estimated Quantities for Slab on Prestressed Concrete Box Beam.



DETAIL "A"



HALF SECTION NEAR Q SPAN

Note:

The contractor shall pour and satisfactorily finish the roadway slab at a rate of not less than 25 cubic yards per hour.

DETAILS OF SLAB REINFORCEMENT

Designed: TPL  
Detailed: CAB  
Checked: KLH



4-7-2011

DATE PREPARED  
3/21/2011

ROUTE STATE

DISTRICT SHEET NO.

15

CITY

FENTON

JOB NO.

1100110

FED.-AID PROJECT NO.

BRM-4989(606)

PROJECT NO.

N/A

BRIDGE NO.

1420013

DESCRIPTION

Revised Beam Camber Diagram

DATE

3/24/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

4/05/11

OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK

DETAILS OF SLAB REINFORCEMENT

**HORNER & SHIFRIN, INC.**  
ENGINEERS  
5200 OAKLAND AVE., ST. LOUIS, MO 63110-1490  
TEL: 314-531-9966 FAX: 314-531-9966 www.horner-shifrin.com  
Professional Engineer License No. 000158  
Expiration Date: December 31, 2012

NOTE: DRAWINGS ARE NOT TO SCALE, FOLLOW DIMENSIONS



4.12.2011

DATE PREPARED  
3/21/2011

ROUTE STATE  
MO

DISTRICT SHEET NO.  
16

CITY  
FENTON

JOB NO.  
1100110

FED.-AID PROJECT NO.  
BRM-4989(606)

PROJECT NO.  
N/A

BRIDGE NO.  
1420013





DESCRIPTION

DATE 4/5/11  
Added Sheet  
4/11/11  
Removed Note


**HORNER & SHIFRIN, INC.**  
ENGINEERS  
5200 OAKLAND AVE. ST. LOUIS, MO 63110-1490  
314-551-4321 FAX: 314-551-6866 www.HornerShifrin.com  
Discipline: Professional Engineering  
Certificate of Authority: 000195  
Expiration Date: December 31, 2012

OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK  
DETAILS OF GUARDRAIL  
SHEET 1 OF 2


NOTE: DRAWINGS ARE NOT TO SCALE, FOLLOW DIMENSIONS




4-5/8" reduced base welded studs. Provide 4-5/8" washers and self-locking nuts or nuts and jam nuts for guardrail connection.




SECTION AT RAIL SPLICE




RAIL SPLICE CONNECTION AT EXPANSION JT.



DETAIL OF 3/4" Ø ROUND HEAD BOLT




With Slot



Without Slot or Recess

VIEW C-C






(5" minimum to 7 1/8" maximum CWS thickness)

4-3/4" Ø x 6" Round Head Bolts (With slot or approved recess in head) with locknut & flat washer. 7/8" Ø holes in hollow structural section may be drilled in the field.

SECTION AT RAIL POST




SECTION A-A



SECTION B-B

Designed: TPL  
Detailed: CAB  
Checked: KLH

DETAILS OF GUARDRAIL



\*Threaded areas shall be plugged or blocked off during casting of beam. Galvanized after fabrication.

Notes:

- \*\* The studs of the anchor devices shall be placed below the top reinforcement bars and the outermost longitudinal reinforcement bar shall be placed directly above the studs of the rail post anchor device.
- Hollow structural sections shall conform to the requirements of ASTM designation A 500 Grade B Structural Steel Tubing and shall meet the longitudinal CVN requirements of 15 ft-lbs at 0°F.
- All other steel shapes and plates shall conform to the requirements of AASHTO M270 Grade 36 except posts and angles shall conform to AASHTO M270, Grade 50.
- Bolts, cap screws, and nuts shall conform to the requirements of ASTM designation A 307 except for high strength bolts, nuts, and washers noted, which shall conform to AASHTO M164.
- All bolts, nuts, cap screws, washers, and lock washers shall be galvanized according to AASHTO M232.
- All posts, railing, rail splices, anchor devices and angles shall be galvanized after shop fabrication according to AASHTO M111 and ASTM A385. Galvanized rail shall not be painted.
- Railing will be paid for at the contract unit price per foot for Bridge Guardrail. All field drilled holes shall be coated with an approved zinc rich paint before erection.
- Place 1/8" fabric bearing pads between the 1/2"x7"x6" plates that come in contact with concrete.
- The 3/4" Dia. high strength bolts used to connect the 6x4x3/4" angles to the post shall be tightened according to the "Specification for Structural Joints using ASTM A325 or ASTM A 490 Bolts" for Slip Critical Connections as issued by the Research Council on Structural Connections Joints of the Engineering Foundation. The 1" Dia. high strength bolts connecting the angles to the concrete shall be tightened to a snug fit and given an additional 1/8 turn. The 5/8" Dia. cap screws in bottom of posts shall be tightened to a snug fit only.
- Stud connectors shall conform to the requirements of AASHTO M169 cold drawn bars, Grade 1015, 1018, or 1020 either semi- or fully-killed. Welding and workmanship shall be according to the requirements of the Bridge Welding Code (BWC).

DETAILS OF GUARDRAIL

Designed: TPL  
Detailed: CAB  
Checked: KLH



4.12.2011

DATE PREPARED  
3/21/2011

ROUTE STATE  
MO

DISTRICT SHEET NO.  
17

CITY  
FENTON

JOB NO.  
1100110

FED.-AID PROJECT NO.  
BRM-4989(608)

PROJECT NO.  
N/A

BRIDGE NO.  
1420013

DESCRIPTION

Added Sheet

Revised Note

DATE

4/5/11

4/11/11

NOTE: DRAWINGS ARE NOT TO SCALE, FOLLOW DIMENSIONS

OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK

DETAILS OF GUARDRAIL  
SHEET 2 OF 2

**HORNER & SHIFRIN, INC.**  
ENGINEERS




5200 OAKLAND AVE. ST. LOUIS, MO 63110-1490  
314-531-4321 FAX: 314-531-6966 www.HornerShifrin.com

Discipline: Professional Engineering  
Certificate No. 001012012  
Expiration Date: December 31, 2012



4.12.11

DATE PREPARED 3/21/2011	
ROUTE	STATE MO
DISTRICT	SHEET NO. 18
CITY FENTON	
JOB NO. 1100110	
FED.-AID PROJECT NO. BRM-4999(606)	
PROJECT NO. N/A	
BRIDGE NO. 1420013	



**GENERAL NOTES**


- Attachment to curb mounted bridge rail shown. Attachment to side mounted bridge rail is similar.
- Thrie beam rail shall be bolted to block-out at all posts.
- All slope ratios are expressed as units of vertical displacement to units of horizontal displacement (V:H).
- All dimensions are in Inches (millimeters) unless otherwise shown.

NOTE: DRAWINGS ARE NOT TO SCALE, FOLLOW DIMENSIONS

**HORNER & SHIFRIN, INC.**  
**ENGINEERS**  
 5200 OAKLAND AVE., ST. LOUIS, MO 63110-1490  
 314-531-4321 FAX 314-531-8986 www.HornerShifrin.com  
 Certificate of Authority: 000159  
 Expiration Date: December 31, 2012


OLD HIGHWAY 141  
 BRIDGE OVER  
 FENTON CREEK  
 DETAILS OF GUARDRAIL TRANSITION  
 SHEET 1 OF 3

Designed: TPL  
 Detailed: CBW  
 Checked: TPL




**SECTION C-C**


Bolts (A307) with washers and self-locking nut, or nut and jam nut. Top bolt  $\frac{7}{8} \times 9$  (22x229). Bottom bolt  $\frac{7}{8} \times 5$  (22x127) for curb mount or  $\frac{7}{8} \times 7$  (22x179) for side mount.




**POSTS 1-7 WOOD BLOCKOUT DETAIL**



**POST 8 WOOD BLOCKOUT DETAIL**



**MODIFIED THRIE BEAM END SHOE DETAIL**



**TRANSITION SECTION**  
 (10 gauge (3.4) rail element)

Designed: TPL  
 Detailed: CBW  
 Checked: TPL



4-12-11

DATE PREPARED

3/21/2011

ROUTE STATE

DISTRICT SHEET NO.

19

CITY

FENTON

JOB NO.

1100110

FED.-AID PROJECT NO.

BRM-4989(606)

PROJECT NO.

N/A

BRIDGE NO.

1420013

DATE DESCRIPTION

4/5/11

Added Street

NOTE: DRAWINGS ARE NOT TO SCALE. FOLLOW DIMENSIONS

OLD HIGHWAY 141  
 BRIDGE OVER  
 FENTON CREEK

DETAILS OF GUARDRAIL TRANSITION  
 SHEET 2 OF 3

**HORNER & SHIFRIN, INC.**  
 ENGINEERS  
 5200 OAKLAND AVE. ST. LOUIS, MO 63110-1490  
 314-531-4321 FAX: 314-531-6966 www.hornerShifrin.com  
 Certificate of Authority: 000159  
 Expiration Date: December 31, 2012





4-12-2011

DATE PREPARED  
3/21/2011

ROUTE STATE  
MO

DISTRICT SHEET NO.  
21

CITY  
FENTON

JOB NO.  
1100110

FED.-AID PROJECT NO.  
BRM-49891(606)

PROJECT NO.  
N/A

BRIDGE NO.  
1420013

DESCRIPTION  
Added Sheet

DESCRIPTION  
Replaced Sh., Removed Curb

DATE

**GENERAL NOTES:**

All concrete for the bridge approach slab and sleeper slab shall be in accordance with Sec 503 (f'c = 4,000 psi).

All joint filler shall be in accordance with Sec 1057 for preformed fiber expansion joint filler, except as noted.

The reinforcing steel in the bridge approach slab and the sleeper slab shall be epoxy coated Grade 60 with Fy = 60,000 psi.

Minimum clearance to reinforcing steel shall be 1 1/2", unless otherwise shown.

The reinforcing steel in the bridge approach slab and the sleeper slab shall be continuous. The transverse reinforcing steel may be made continuous by lap splicing the #4 & #6 bars 18" and 2'-2", respectively.

Mechanical bar splices shall be in accordance with Sec 706.

Hooks and bends shall be in accordance with the CRSI Manual of Standard Practice for Detailing Reinforced Concrete Structures, Stirrup and Tie Dimensions.

The contractor shall pour and satisfactorily finish the bridge or semi-deep slab before pouring the bridge approach slabs.

Longitudinal construction joints in approach slab and sleeper slab shall be aligned with longitudinal construction joints in bridge or semi-deep slab.


Payment for furnishing all materials, labor and excavation necessary to construct the approach slab, including the timber header, sleeper slab, underdrain, Type 5 aggregate base, joint filler and all other appurtenances and incidental work as shown on this sheet, complete in place, will be considered completely covered by the contract unit price for Bridge Approach Slab (Bridge) per square yard.

For Concrete Approach Pavement details, see roadway plans.

At the contractor's option, Grade 40 reinforcement may be substituted for the Grade 60 #5 dowel bars connecting the bridge approach slab to the bridge abutment. No additional payment will be made for this substitution.

When Grade 40 reinforcement is substituted for the Grade 60 #5 dowel bars connecting the bridge approach slab to the bridge abutment, the reinforcement may be bent up to 90 degrees with a 2" minimum radius near the abutment to allow compaction of the backfill material near the abutment. Damage to epoxy coating shall be repaired in accordance with Sec 710.


Drain pipe may be either 6" diameter corrugated metallic-coated pipe underdrain, 4" diameter corrugated polyvinyl chloride (PVC) drain pipe, or 4" diameter corrugated polyethylene (PE) drain pipe.



PART PLAN SHOWING REINFORCEMENT


PART PLAN (SHOWING TYPICAL UNDERSEAL ACCESS HOLE LOCATIONS)

Note: Guardrail not shown for clarity.




SECTION B-B


Note: With the approval of the engineer, the contractor may crown the bottom of the approach slab to match the crown of the roadway surface.




DETAILS OF TIMBER HEADER




CONST. JOINT DETAIL



TYPICAL UNDERSEAL ACCESS HOLE DETAIL




#4 STIRRUP BAR (ACTUAL LENGTH = 8'-3")



TYPICAL 135° STIRRUP HOOK DIMENSIONS BENDING DIAGRAM

Note: Nominal lengths are based on out to out dimensions shown in bending diagram and are listed for fabricators use (nearest inch).



SECTION C-C

BRIDGE APPROACH SLAB (Bent 2 shown, Bent 1 similar)

Designed: TPL  
Detailed: TPL  
Checked: CBW

NOTE: DRAWINGS ARE NOT TO SCALE. FOLLOW DIMENSIONS

**HORNER & SHIFFRIN, INC.**  
ENGINEERS

5205 OAKLAND AVE., ST. LOUIS, MO 63112-1490  
314-531-4321 FAX: 314-631-6966 www.hornerShiffin.com  
Discipline: Professional Engineering  
Certificate of Authority: 000159  
Expiration Date: December 31, 2012

OLD HIGHWAY 141  
BRIDGE OVER  
FENTON CREEK

DETAILS OF APPROACH SLAB

**BILL OF REINFORCING STEEL**

NO. REQ'D.	MARK NO.	LOCATION	EPOXY (E)	SHAPE NO.	STIRRUP (S)	SUBSTR. (X)	VARIES (V)	DIMENSIONS							NOMINAL LENGTH	ACTUAL LENGTH	WEIGHT									
								B		C		D		E				F		H		K				
								FT.	IN.	FT.	IN.	FT.	IN.	FT.				IN.	FT.	IN.	FT.	IN.	FT.	IN.	FT.	IN.
		SUBSTR.																								
		END BENT 1																								
64	6 F101	BRIDGE FTG		20				8	8.000						8	8	8	833								
106	7 F102	BRIDGE FTG		19				8	5.000	5	8.000				14	13	11	3015								
15	4 F103	BRIDGE FTG		20				52	11.000						52	11	52	530								
61	6 F104	WING FTG		20				9	5.000						9	5	9	863								
110	7 F105	WING FTG		19				8	5.000	4	11.000				13	4	13	2960								
15	4 F106	SOUTH FTG		20				31	3.000						31	3	31	313								
	F107	NOT USED																								
3	6 F108	NORTH FTG		20			V	1	6	10.000					6	10	6	10								
		INCREMENT =						9	5.000						9	5	9	37								
		15.50 INCH																								
5	6 F109	NORTH FTG		20				5	6.000						5	6	5	41								
8	6 F110	NORTH FTG		20				9	5.000						9	5	9	113								
15	4 F111	NORTH FTG		20				18	6.000						18	6	18	185								
15	4 F112	NORTH FTG		20				5	3.000						5	3	5	53								
4	6 H1	DIAPHRAGM	E	20				52	11.000						52	11	52	318								
3	6 H3	DIAPHRAGM		20				52	11.000						52	11	52	238								
18	4 H5	DIAPHRAGM		20				3	3.000						3	3	3	39								
52	5 H10	DIAPHRAGM	E	20				2	6.000						2	6	2	136								
15	4 H101	BRIDGE WALL		20				52	11.000						52	11	52	530								
10	4 H102	BRIDGE WALL		20				52	11.000						52	11	52	353								
7	4 H103	SOUTH WING		20				21	1.000						21	1	21	99								
10	4 H104	SOUTH WING		20				21	3.000						21	3	21	142								
5	4 H105	SOUTH WING		20			V	1	7	1.000					7	1	7	1								
		INCREMENT =						19	1.000						19	1	19	44								
		36.00 INCH																								
7	4 H106	SOUTH WING		20			V	1	7	3.000					7	3	7	3								
		INCREMENT =						19	3.000						19	3	19	62								
		24.00 INCH																								
12	4 H107	SOUTH WING		20				9	3.000						9	3	9	74								
17	4 H108	SOUTH WING		20				9	5.000						9	5	9	107								
2	6 H109	SOUTH WING		15				2	11.750	16	1.000	2	11.750	1	4.000	2	8.000	2	8.000	1	4.000	22	1	22	0	66
17	4 H110	NORTH WING		15				22	2.000	3	0.125	2	9.875	1	0.375	25	2	25	1	285						
12	4 H111	NORTH WING		15				20	10.000	1	9.875	1	8.500	0	7.500	22	8	22	7	181						
28	6 H112	NORTH WING		20				7	6.000						7	6	7	6	315							
2	6 H113	NORTH WING		20				8	9.000						8	9	8	9	26							
8	6 H114	NORTH WING		20				5	6.000						5	6	5	6	66							
12	6 H115	NORTH WING		20				9	0.000						9	0	9	0	162							
24	5 U4	DIAPHRAGM	E	10				2	3.000	2	4.750				6	1	6	8	167							
69	6 U5	DIAPHRAGM	E	19				2	3.000	5	6.000				7	9	7	7	786							
24	6 U6	DIAPHRAGM		19				1	3.000	2	11.000				4	2	4	0	144							
63	4 U7	BRIDGE WALL		10				0	6.000	2	11.000				3	1	3	9	158							
6	6 U8	DIAPHRAGM		10				1	1.000	2	3.000				4	5	4	1	37							
56	5 V1	BRIDGE WALL		20				3	4.000						3	4	3	4	195							
42	6 V2	DIAPHRAGM		20				1	4.000						1	4	1	4	64							
8	5 V3	BRIDGE WALL		20				4	3.000						4	3	4	3	35							
36	4 V10	BRIDGE WALL		20				13	11.000						13	11	13	11	335							
106	6 V102	BRIDGE WALL		20				13	11.000						13	11	13	11	2216							
33	6 V103	SOUTH WING		20				16	7.000						16	7	16	7	822							
29	6 V104	SOUTH WING		20			V	1	9	5.000					9	5	9	5								
		INCREMENT =						16	5.000						16	5	16	5	563							
		3.00 INCH																								

**BILL OF REINFORCING STEEL**

NO. REQ'D.	MARK NO.	LOCATION	EPOXY (E)	SHAPE NO.	STIRRUP (S)	SUBSTR. (X)	VARIES (V)	NO. EACH	DIMENSIONS							NOMINAL LENGTH	ACTUAL LENGTH	WEIGHT							
									B		C		D		E				F		H		K		
									FT.	IN.	FT.	IN.	FT.	IN.	FT.				IN.	FT.	IN.	FT.	IN.	FT.	IN.
10	4 V105	SOUTH WING		20				1	9	5							9	5	9	5	87				
		INCREMENT =							16	6.000							16	6	16	6	87				
		9.50 INCH																							
12	4 V106	SOUTH WING		20					16	7.000							16	7	16	7	133				
46	6 V107	NORTH WING		20					16	9.000							16	9	16	9	1157				
17	6 V108	NORTH WING		20					16	9.000							16	9	16	9	428				
12	6 V109	NORTH WING		20			V	2	6	6.000							6	6	6	6	147				
		INCREMENT =							9	10.000							9	10	9	10	147				
		8.00 INCH																							
8	6 V115	NORTH WING		20					9	0.000							9	0	9	0	108				
		SUPERSTR.																							
		END BENT 2																							
4	7 H21	DIAPHRAGM	E	20					50	10.000							50	10	50	10	416				
8	7 H22	BEAM		20					50	10.000							50	10	50	10	831				
7	6 H23	BEAM & DIAPH		20					50	10.000							50	10	50	10	534				
4	6 H24	BEAM		20					5	0.000							5	0	5	0	30				
18	4 H25	DIAPHRAGM		20					3	3.000							3	3	3	3	39				
16	6 H27	WING		20					9	3.000							9	3	9	3	222				
4	6 H28	WING	E	20					5	3.000							5	3	5	3	32				
4	6 H29	WING		20					7	7.000							7	7	7	7	46				
52	5 H30	DIAPHRAGM	E	20					2	6.000							2	6	2	6	136				
20	5 U21	BEAM		11					4	4.000	2	11.000	5	3.000			12	6	12	3	256				
51	4 U22	BEAM		13					2	11.000	2	7.500	2	11.000	2	7.500	11	10	11	6	392				
12	4 U23	BEAM		10					2	7.500	2	11.000	2	11.000			8	2	8	0	64				
24	5 U24	DIAPHRAGM	E	10					2	3.000	2	4.750					6	11	6	8	167				
69	6 U25	DIAPHRAGM	E	19					2	3.000	5	6.000					7	9	7	7	786				
24	6 U26	DIAPHRAGM		19					1	3.000	2	11.000					4	2	4	0	144				



Old Highway 141 Bridge  
Fenton, Missouri

**LOG OF BORING 1**

PROJECT NO. 10395      DATE: 3/9/04      LOCATION: See Figure 1

DEPTH, FT.	COMPLETION DEPTH 36.0 FT.	STRATUM DEPTH, FT.	SPT BLOWS/6 in. THREE 6-in. INCREMENTS	DISTURBED SAMPLE	PERCENT RECOVERY	ROCK CORE	Shear Strength from Indicated Test, tsf												
							1	2	3	4	5								
	BORING METHOD CFA-RC						Dry Density, pcf 80    90    100    110    120												
	ROCK CORE DIAMETER    IN.						Plastic Limit    Water Content, %    Liquid Limit Standard Penetration Resistance, Blows/Ft. 10    20    30    40    50												
	SURFACE ELEVATION 412.2 FT.																		
5	Brown Clay and Silty Clay with trace fine gravel (FILL)		2				⊗												
7.0	Gray Clayey Silt (FILL)																		
10	Gray medium stiff Clayey Silt (ML)	9.2	5				⊗												
12.0	Brown mottled medium stiff Silty Clay (CL) with trace gravel		2				⊗												
15			3																
17.5	Brown very stiff Clay (CH) with some gravel		6																
20			12																
20.5	Weathered Limestone and Chert	21.0																	
21.0	Light gray and tan thin- to medium-bedded fine-grained crystalline Limestone with intermittent chert and occasional weathered partings																		
25	-4.5 in. clay seam at 24.3 feet		ROD 50		93														
30			45		100														
35	Boring terminated at 36.0 feet	36.0	37		93														

WATER LEVEL OBSERVATIONS		NOTES
DURING DRILLING	17.5 FT.	Hard coring: 36 minutes to advance core barrel 4 inches at 28.5 feet.
AT COMPLETION	FT.	
AFTER	HRS. FT.	

Shear Test Types - Direct Shear: ● Torvane: ■ Unconf. Compr.: ▼ Miniature Vane: ▲ Field Vane: ◆

MIDWEST TESTING

Old Highway 141 Bridge  
Fenton, Missouri

**LOG OF BORING 2**

PROJECT NO. 10395      DATE: 3/9/04      LOCATION: See Figure 1

DEPTH, FT.	COMPLETION DEPTH 23.0 FT.	STRATUM DEPTH, FT.	SPT BLOWS/6 in. THREE 6-in. INCREMENTS	DISTURBED SAMPLE	PERCENT RECOVERY	ROCK CORE	Shear Strength from Indicated Test, tsf												
							1	2	3	4	5								
	BORING METHOD CFA-RC						Dry Density, pcf 80    90    100    110    120												
	ROCK CORE DIAMETER    IN.						Plastic Limit    Water Content, %    Liquid Limit Standard Penetration Resistance, Blows/Ft. 10    20    30    40    50												
	SURFACE ELEVATION 414.8 FT.																		
5	5 in. Asphalt 4 in. Crushed Stone Brown mottled medium stiff Silty Clay (CL)		2				⊗												
4.5	Brown medium stiff Clay (CH) with trace gravel		3																
7.5	Weathered Limestone and Chert	8.0																	
10	4 in. Gray Limestone 9 in. Brown Clay with trace sand 7 in. Gray Limestone 12 in. Gray Clay with trace sand Light gray and tan thin- to medium-bedded fine-grained crystalline Limestone with intermittent chert and occasional weathered partings	10.7																	
15			ROD 55		83														
20			56		93														
25	Boring terminated at 23.0 feet	23.0																	

WATER LEVEL OBSERVATIONS		NOTES
DURING DRILLING	Dry FT.	
AT COMPLETION	FT.	
AFTER	HRS. FT.	

Shear Test Types - Direct Shear: ● Torvane: ■ Unconf. Compr.: ▼ Miniature Vane: ▲ Field Vane: ◆

MIDWEST TESTING

WOOLPERT INC  
4454 IDEA CENTER BLVD.  
DAYTON, OHIO 45430  
937.461.5660




**OLD HIGHWAY 141  
ROADWAY IMPROVEMENT PLANS**  
FENTON, MISSOURI  
Prepared For:  
**CITY OF FENTON**

825 N.W. SWEET MILL ROAD  
FENTON, MISSOURI 63824  
(636) 349-0110

REVISIONS NO.	DATE

ENGINEERS AUTHENTICATION  
The responsibility for professional engineering liability on this project is hereby limited to the set of plans authenticated by the seal, signature, and date hereunder attached. Responsibility is disclaimed for all other engineering plans involved in this project and specifically excludes revisions after this date unless reauthenticated by the engineer.



Michael A. Avellano  
4-12-10

DRAWN	RACH	DATE	APRIL-2010
CHECKED	B.W.B.	DATE	APRIL-2010
PROJECT #	061923	TASK #	01
		FIELD BOOK	

OLD HIGHWAY 141  
ROADWAY IMPROVEMENT PLANS  
SOIL BORING LOGS  
**SHEET B-17**  
© Copyright 2004 by Woolpert, LLP

PRINTED Apr 01, 2010 - 11:13am FILENAME - G:\FD\Clients\Bridges\City of Fenton, Ill (Old 141)\CAD\B17-502.dwg



5200 Oakland Ave.  
St. Louis MO 63110-1490  
(314) 531-4321 • Fax: (314) 531-6966

640 Pierce Blvd., Suite 200  
O'Fallon, IL 62269-2579  
(618) 622-3040 • Fax: (618) 622-3070

April 6, 2011

Mr. Sean Kilian  
L. Krupp Construction, Inc.  
415 Old State Road  
Ellisville, MO 63021

**Re: Value Engineering of Fenton Creek Bridge Replacement  
Project No. BRM-4989(606), Bridge No. 1420013  
Response to Review Comments and Revised Final Plans**

We have reviewed the comments from CDG and have provided our responses below. Our comments are in red. Revised plans based on these comments are attached.

**General Comments:**

1. Drawings and calculations were reviewed for general content and agreement only. A detailed check of the drawings and calculations was not undertaken. **Noted.**
2. The SI&A Form and Load Rating with supporting calculations were received on April 1, 2011 and are acceptable. **Noted.**
3. An updated cost estimate was received on April 1, 2011. The estimate will be reviewed and comments returned on or around April 6, 2011. **Noted.**
4. Need cost comparison of design with soldier pile wall (original Krupp VE concept) versus full-height abutment on spread footing (current Krupp VE proposal) for End Bent No. 1. This constitutes a major design change with minimal justification provided to support the change (reference March 21, 2011 letter from Horner & Shifrin to L. Krupp Construction, item 3).

**Final design for Abutment 1 showed that cantilevered soldier pile walls could not be realistically achieved due to anticipated maximum wall height. The section of the wall under the bridge could be designed as a propped cantilever with the superstructure bracing the top of the wall, but would require piles spaced at around 4'. Because the wing walls could not be reasonably designed as a soldier pile wall, it was decided to found the entire abutment on spread footings.**

5. Bridge will be overtopped per the Hydraulic analysis as indicated in the Hydrologic Data Table on Sheet B-2 of the Woolpert Plans. Were buoyancy (uplift) and/or stream flow pressure considered in design? **Vent holes will be added per Comment #39.**
6. Verify that providing spread footings (End Bent No. 1) keyed 6" into rock with riprap placed as shown in Roadway Plans is adequate to anchor the footings and protect against scour. Are mechanical rock anchors needed? **The footings are keyed 6" into sound rock. There is approximately 1'-3' of weathered rock above sound rock per the borings and riprap above that. I have attached excerpts from**

a report by the University of Kentucky on the susceptibility of rock scour based on RQD values. We do not believe scour to be an issue for this project based on this research.

7. VE Submittal indicates that Woolpert Sheet Nos. B-2, B-12 (Bridge Railings & Details), B-13 (Bridge Rail Transition Details) B-15 (Bridge Approach Slab) & B-17 (Soil Boring Logs) will be re-used. The Hydrologic Data Table shown on Sheet No. B-2 should be incorporated into Sheet No. 2 as indicated in comment No. 8 below; remaining portion of Woolpert Sheet No. B-2 is not needed. It is OK to retain Sheet B-17 for information only. Other Sheets should not be re-used under Woolpert seal. The information in these drawings should be incorporated into drawings sealed by the Contractor's Engineer. **Plans revised accordingly.**

### **Drawing Review Comments:**

#### **Sheet No. 1 – General Plan & Elevation (Drawing date: 3/21/11)**

8. "Notice and Disclaimer Regarding Boring Log Data" should refer to the *City of Fenton*, not *department* or *district*. **Plans revised accordingly.**

#### **Sheet No. 2 – Estimated Quantities, Foundation Data & General Notes (Drawing date: 3/21/11)**

9. Add Hydrologic Data table shown on Woolpert Drawing B-2 and identify this table as "taken from Drawing B-2 of the original design plans". **Plans revised accordingly.**
10. All excavation above the Excavation Datum (defined as Elev. 399.00 on Sheet No. 1) is Class 1 Excavation. Where is Class 1 Excavation in Rock? Is this a placeholder quantity? Quantity calculations indicate 10 CY pulled out of Class 1 with no further explanation.

**The only rock excavation is for the 6" key; and the bottom of footing elevation should be adjusted per the note on Sh. 3. The plans assume this is Class 2 Excavation in Rock. Since it is possible that sound rock could be encountered above the Excavation Datum Elevation, a placeholder quantity for Class 1 Excavation in Rock is used to facilitate construction should Class 1 Rock be encountered.**

11. All excavation below the Excavation Datum is Class 2 Excavation. The quantity for Class 2 Excavation in Rock appears to cover only the removal of rock for the 6" key under the footprint of abutment and wingwall footings at End Bent No. 1. Is this the only rock excavation anticipated as Class 2? **The only rock excavation is for the 6" key. Weathered rock should be measured as Class 1 or Class 2 Excavation.**
12. Add note below ESTIMATED QUANTITIES table: *Cost of channel shear connectors C4x5.4 (ASTM A709 Grade 36) in place will be considered completely covered by the contract unit price for Structural Steel Piles (12 in.). This is required per MoDOT Engineering Policy Guide (EPG), Section 751.50, Standard Note B3.2 for Seismic Performance Category B.* **Plans revised accordingly.**
13. Add note below ESTIMATED QUANTITIES FOR SLAB ON PRESTRESSED BOX BEAM table: *The Estimated Quantities for Slab on Prestressed Concrete Box Beam are based on skewed precast prestressed end panels (Ref. EPG, Section 750.50, Standard Note B3.40).* **Plans revised accordingly.**
14. Add note under GENERAL NOTES, Neoprene Pads: *Bearings shall be (H&S specified durometer) durometer neoprene pads (Ref. EPG, Section 751.50, Standard Note A3.2).* **Plans revised accordingly.**

15. Add note under GENERAL NOTES, Miscellaneous: "*Sec*" refers to the sections in the standard and supplemental specifications unless specified otherwise (Ref. EPG, Section 751.50, Standard Note A5.5). **Plans revised accordingly.**
16. Remove note under GENERAL NOTES for Protective Coating. This is only required with structural steel. **Plans revised accordingly.**
17. Adjust reinforcing steel quantities as required for changes indicated on other sheets. **Plans revised accordingly.**

Sheet No. 3 - Details of End Bent No. 1 (EB No. 1, Sheet 1 of 5) (Drawing date 3/28/11)

18. Revise callout in PLAN OF BEAM SHOWING DIMENSIONS to remove reference to *Centerline Pile*. **Plans revised accordingly.**

Sheet No. 4 - Details of End Bent No. 1 (EB No. 1, Sheet 2 of 5) (Drawing date 3/28/11)

19. No comments.

Sheet No. 5 - Details of End Bent No. 1 (EB No. 1, Sheet 3 of 5) (Drawing date 3/21/11)

20. Callout in PLAN OF BEAM SHOWING REINFORCEMENT on right side indicates *15-#4-F106 bars* (See Section C-C for placement). Section C-C on Sheet No. 6 indicates *10-#4-F106 @ 12"*. Which is correct? Correct BILL OF REINFORCING STEEL on Sheet No. 16 if required. **15 bars is correct – there are 10 top bars and 5 bottom bars as shown in the section.**
21. Should V108 bars called out on left side of PLAN OF BEAM SHOWING REINFORCEMENT be #4 bars instead of #6 bars as shown for other front face reinforcement (#4-V105 & #4-V106)? If so, revise callout and correct BILL OF REINFORCING STEEL on Sheet No. 16. **V108 bars should be #4, Sh. 2, 5, 7 and 16 have been revised accordingly.**
22. Revise callout to read *End of Box Beam* instead of *End of Girder* in ANCHOR ROD DETAIL. **Plans revised accordingly.**

Sheet No. 6 - Details of End Bent No. 1 (EB No. 1, Sheet 4 of 5) (Drawing date 3/21/11)

23. See comments for #4-F106 & F107 bars noted under Sheet No. 5. **See response to note. 20.**
24. See comments for #4-F111 & F112 bars noted under Sheet No. 7. **See response to note. 28.**
25. Revise callouts on Sections A-A & C-C to refer to *Riprap* instead of *Finished Ground Line* or remove callouts. **Callouts removed.**
26. Add additional dimensions for footings to clarify intent in Sections A-A & C-C. **I assume you are referring to the dimensions of the bottom of stem and heel. These dimensions were intentionally not shown because they vary based on wall height due to battered stream face of stem. The wall height varies due to varying sound rock elevations. See note under Developed Section on Sh. 3.**

27. Add elevation callout at bottom of footings for Section A-A & C-C. **The elevations were intentionally left off because bottom of footing is tied to sound rock elevations which vary. For quantity purposes, a sound rock elevation of 397.00 was assumed as shown on Sh. 3. The elevations were not shown in sections to help reinforce that rock elevations vary.**

Sheet No. 7 - Details of End Bent No. 1 (EB No. 1, Sheet 5 of 5) (Drawing date 3/21/11)

28. FOOTING PLAN OF NORTH WING SHOWING REINFORCEMENT calls out 15-#4-F111 & 15-#4-F112 (See Section C-C for placement). These callouts should refer to Section D-D (which is noted as being similar to Section C-C) on Sheet No. 6. Section C-C on Sheet No. 6 indicates 10-#4-F106 or F107 @ 12". This would seem to indicate that there would also be 10-#4 F111 or F112 bars. Is this correct? Correct BILL OF REINFORCING STEEL on Sheet No. 16 if required. **Callout revised to Section D-D; 15 bars is correct – see response to note 20.**
29. Clarify size of block-out for 66" Pipe (no size is explicitly provided). Is intent to have min. of 3" from pipe for approx. 72" square opening? **Your interpretation is correct – no clarification warranted. Verify that additional reinforcement provided around block-out is adequate? . The additional reinforcement is adequate and exceeds that required by MoDOT Standard Plan 703.60.**

Sheet No. 8 - Vertical Drain Details (Drawing date 3/21/11)

30. No comments

Sheet No. 9 - Details of End Bent No. 2 (EB No. 2, Sheet 1 of 3) (Drawing date 3/21/11)

31. Revise callout to read *Box Beam Spacing* instead of *Girder Spacing* in PLAN OF BEAM SHOWING DIMENSIONS. **Plans revised accordingly.**
32. Revise callout to read *End of Box Beam* instead of *End of Girder* in ANCHOR ROD DETAIL. **Plans revised accordingly.**
33. Remove or revise note below PLAN OF BEAM SHOWING REINFORCEMENT stating "*Cut or bend U1 and V1 bars to fit*". These bars are not in End Bent No. 2. **Plans revised accordingly.**

Sheet No. 10 - Details of End Bent No. 2 (EB No. 2, Sheet 2 of 3) (Drawing date 3/28/11)

34. Revise callout to read 4-#4-U27 instead of 4-#4-U7 in SECTION NEAR END BENT. **Plans revised accordingly.**
35. Revise callout to read 1-#6-H23 instead of 1-#6-H3 in PART PLAN. **Plans revised accordingly.**
36. Add MoDOT Standard detail showing channel shear connectors for piles (see comment No. 11 above). **Plans revised accordingly.**

Sheet No. 11 - Details of End Bent No. 2 (EB No. 2, Sheet 3 of 3) (Drawing date 3/28/11)

37. Revise Elevation callout at bottom of beam to read *Elev. 409.10* in SECTION B-B. **Plans revised accordingly.**

38. Revise bar callout to read #4-U27 instead of #4-U7 in SECTION C-C. **Plans revised accordingly.**

Sheet No. 12 - Details of Precast Prestressed 48" Box Beams (Sheet 1 of 2) (Drawing date 3/21/11)

39. Is there some way to provide a 3" diameter vent hole at or near the upgrade 1/3 point of the beams similar to that shown in EPG Section 751.22.3.16 for P/S I-girders? We do not want to fill the voids in the beams with water but could the vent hole be sleeved with PVC or other to permit trapped air between the box beams to escape as water rises above the beams and remain water tight? Vent holes were not needed with adjacent box beams but the VE redesign provides spread boxes. This bridge will be overtopped as indicated in the Hydrologic Data Table on Sheet B-2 of the original Woolpert plans. **A 3" vent hole was added thru the solid section of the box near the upgrade end and the void length was modified to accommodate this.**

Sheet No. 13 - Details of Precast Prestressed 48" Box Beams (Sheet 2 of 2) (Drawing date 3/21/11)

40. No comments

Sheet No. 14 – Details of Precast Prestressed Panels (Drawing date 3/21/11)

41. No comments

Sheet No. 15 – Details of Slab Reinforcement (Drawing date 3/24/11)

42. Revise callout in HALF SECTION NEAR CENTERLINE SPAN to state *21x48 PPC Box Beam (Typ.)* instead of *Deck Beam*. **Plans revised accordingly.**

Sheet No. 16 - Bill of Reinforcing Steel (Drawing date 3/21/11)

43. Not reviewed

Sheet No. 17

44. Not included in Plan Set. Please provide for review or renumber accordingly. **Plans revised accordingly.**

Sheet No. 18 – As-Built Data Sheet (Drawing date 3/21/11)

45. No comments

Sincerely,



Michael A. Banashek, P.E.  
Structural Department Manager

# L. Krupp Construction, Inc.

April 7, 2011

Dan Howard  
City of Fenton  
625 New Smizer Mill Road  
Fenton, MO 63026

RE: Fenton Creek Bridge Replacement  
Old Highway 141; Bridge #1420013  
Project No. BRM-4989 (606)

Subject: **Value Engineering Proposal Pricing Answers**

Dear Mr. Howard:

As per the request of Glenn Smith, the following is a list of answers to questions submitted via e-mail on 4/5/2011:

- 1. CDG COMMENT: In the Final 3/29/11 Krupp VE Estimate, Class 1 Excavation in Rock and Class 2 Excavation in Rock have the same unit price of \$150/CY. (Class 1 and 2 definitions are based on an elevation datum but it doesn't matter on this project since Class 1 and 2 unit prices are equal.) Estimated quantities for both Class 1 (10 CY) and Class 2 (19 CY) rock excavations are small. The Class 2 Rock Excavation quantity is the footing area (998.4 SF) x 6" = 18.49 CY (rounded to 19 CY). There is considerable risk with spread footing on rock in that these quantities could grow in the field substantially increasing the cost during construction. These Class 1 and 2 Rock Excavation pay items are new in the 3/28/11 estimate using spread footing on rock versus original the 3/14/11 VE conceptual design of piles with a CIP wall.**

*KRUPP ANSWER: I'm not sure exactly how to "answer" this question/statement. However, I believe this would be a good opportunity to restate the inherent risk associated with proceeding with construction as currently planned. Should rock be where everyone assumes it is, we would be involved in a long and costly redesign, possibly to arrive at this exact design. The average unit prices for MoDOT from last year for these item were: Class 1 Excavation in Rock = \$225.50 for an average quantity of 57.68 CY and Class 2 Excavation in Rock = \$249.92 for an average quantity of 40.71 CY. As you can see, average quantities are more that double what we have, but our prices are 1/3 lower.*

- 2. The Class B Concrete Substructure unit price has increased twice from the original Krupp bid unit price as follows:**

**\$385/CY original Krupp bid (based on 371 CY)  
Asphalt Paving and Excavation**

**\$516/CY 2/14/11 Krupp Conceptual VE Estimate (based on 175 CY)**

**\$535/CY 3/29/11 Krupp Final VE Estimate (based on 252.1 CY)**

**It seems like the unit price should not have increased in the 3/29/11 VE Final Estimate with a larger quantity compared to the 2/14/11 Conceptual Estimate. Please explain.**

*Krupp Answer: In the original bid, the footing quantity (which is the high production, low cost item) was approximately 190 CY, or 46% of the total Class B bid. In the redesign, that footing quantity has gone down to approximately 70 CY, or 28% of the total Class B item. Due to the large reduction in this item, the average unit cost increased significantly, thus increasing the unit price. For comparative reasons, I'm not going to include the conceptual VE estimate as that was based on vague assumptions of what the final product may be and not an actual set of plans. The average unit price for Class B Substructure for MoDOT last year was \$552.85 for an average quantity of 175.55 CY. Our price is lower, but we also have more quantity.*

- 3. Unit price for Slab on Concrete I-Girder was \$111/SY for a total of \$33,522 in the 2/14/11 Krupp Conceptual VE Estimate. Unit price for Slab on Prestressed Concrete Box Beam is now \$235/SY for a total of \$72,380 in the 3/29/11 Krupp Final VE Estimate. Both of these unit prices were based on a spread box beam arrangement with 7 box beams. Why did this unit price increase, (more than doubled)?**

*Krupp Answer: As mentioned above, this is comparing a guess to an actual estimate. However, there are a couple of things to note. In the conceptual VE, all rebar and placement was under the rebar items. With the final submittal for this item, approximately 12,900 pounds of rebar plus placement were moved from the rebar items and included in this item. Additionally and more importantly, I did not account for forming, pouring, stripping, nor materials for diaphragms in the conceptual VE proposal. The average unit price for Slab on Concrete I-Girder for MoDOT last year was \$246.05 for an average quantity of 1,125.65 SY. Again, our price is lower even with a quantity that is only 27% the average quantity.*

- 4. The Prestressed Concrete Box Beams (55' Span) were bid at \$12,500 Each, for 14 adjacent box beams (\$150,000 total) in the original Krupp bid. In the 2/14/11 Krupp Conceptual VE Estimate the Prestressed Concrete Box Beam (21") were estimated at \$14,000 for a total of \$98,000 for the 7 spread box beams. In the 3/29/11 Krupp Final VE Estimate the Prestressed Concrete Box Beam (21") were estimated at \$18,150 for a total of \$127,050 for the 7 spread box beams. Why did this unit price increase between the two VE estimates? It seems like the price to now provide one-half the number of box beams compared to the original Krupp bid should be lower. (\$127,050 vs. \$150,000)**

*Krupp Answer: There are numerous reasons for the increase in this unit price for this item. First, please note that we are not proposing to provide one-half the number of beams as compared to the original, rather 7 out of 12. Second, the new beams are heavier, have more strands, and are more costly to build. I was unable to use my original supplier for these beams, which is what the Conceptual*

*VE was based upon. In addition to the new beams being more expensive, I also had to add precast panels and the placement of those panels to the cost, something that was not in the original bid and something that I underestimated the cost of for the Conceptual VE. Unfortunately, MoDOT does not have an average for this size box beam.*


- 5. The overall projected savings in the 2/14/11 Krupp Conceptual VE Estimate was \$63,304.50. The overall projected savings in the 3/29/11 Krupp Final VE Estimate is \$63,148.25. These two numbers are surprisingly close. There is now more risk to the City and the projected savings with the current Final VE proposal compared with the Conceptual VE proposal. That risk is due to the uncertainty in rock elevations and possible changes to rock excavation, additional Class B concrete, rebar, etc. that may be required to field adjust the End Bent 1 spread footing to meet actual conditions.**

*Krupp Answer: I was just as surprised when I arrived at the final cost savings. However, due to the change in engineering fees this week, that savings has changed. In regards to the risk, I truly believe that this VE eliminates a huge risk for the city when considering the potential changes and delays based upon rock elevations encountered in the field.*

Lastly, the new DBE info was submitted along with the revised Value Engineering form.

If you have any additional questions, please contact me at (314) 280-0353.

Sincerely,



Sean Kilian  
Project Manager



5200 Oakland Ave.  
St. Louis MO 63110-1490  
(314) 531-4321 • Fax: (314) 531-6966

640 Pierce Blvd., Suite 200  
O'Fallon, IL 62269-2579  
(618) 622-3040 • Fax: (618) 622-3070

---

April 12, 2011

Mr. Sean Kilian  
L. Krupp Construction, Inc.  
415 Old State Road  
Ellisville, MO 63021

**Re: Value Engineering of Fenton Creek Bridge Replacement  
Project No. BRM-4989(606), Bridge No. 1420013  
Response to Review Comments and Revised Final Plans**

We have reviewed the comments from CDG in their letter dated April 11, 2011 and have provided our responses below. Our comments are in red. Revised plans based on these comments are attached.

**General Comments:**

9. Linework on added drawings is light and difficult to read in PDF files we received. Please modify for appearance consistent with other drawings and provide new PDF files. **Sh. 18 thru 20 were re-plotted using the correct pen table.**

**Added - Sheet No. 16 – Details of Guardrail (Sheet 1 of 2) (Drawing date 4/7/11)**

25. Verify that location of 1" diameter x 7 ¾" AASHTO M164 Anchor Bolts shown 6" below top of beam in SECTION AT RAIL POST will work with P/S strands shown 5 ¼" below top of beam in SECTION B-B on Sheet No. 12. It appears that the anchor bolts and P/S strands may conflict. **There is approximately 1.5" clearance to the strands which is adequate.**
26. Revise note at bottom left that refers to "5" minimum to 7 1/8" maximum CWS thickness". The CWS (concrete slab) thickness provided is 8½". **Note was revised.**

**Added - Sheet No. 17 – Details of Guardrail (Sheet 2 of 2) (Drawing date 4/7/11)**

27. Callout for HSS on PL 1/2" x 7" x 6" detail is unreadable. Please revise. **Note was revised.**


**Added - Sheet No. 20 – Details of Guardrail Transition (Sheet 3 of 3) (Drawing date 4/7/11)**

30. Remove or "X out" details for BASE PLATE, SPACER PLATE and FLUSH MOUNTED POST ANCHOR DETAIL or indicate where these apply. **Details were X'd-out.**

Added - Sheet No. 21 – Details of Approach Slab (Drawing date 4/7/11)

31. PART PLAN SHOWING REINFORCEMENT, PART PLAN and SECTION B-B show and/or callout Type A curb at the edges of the approach slabs. Remove all references and depictions of Type A curb. No curb will be provided. **This sheet was modified and completely replaced to remove the Type A curb.**
32. Remove section cut for Section E-E shown on PART PLAN SHOWING REINFORCEMENT. **Section was removed.**

Sincerely,

A handwritten signature in black ink that reads "Michael A. Banashek". The signature is written in a cursive, slightly slanted style.

Michael A. Banashek, P.E.  
Structural Department Manager

Old Highway 141 Bridge  
Fenton, Missouri

**LOG OF BORING 1**

PROJECT NO. 10395      DATE: 3/9/04      LOCATION: See Figure 1

DEPTH, FT.	COMPLETION DEPTH 36.0 FT.	STRATUM DEPTH, FT.	SPT BLOWS/6 in. THREE 6-in. INCREMENTS	DISTURBED SAMPLE	PERCENT RECOVERY	ROCK CORE	Shear Strength from Indicated Test, tsf												
							1	2	3	4	5								
	BORING METHOD CFA-RC						Dry Density, pcf 80    90    100    110    120												
	ROCK CORE DIAMETER    IN.						Plastic Limit    Water Content, %    Liquid Limit Standard Penetration Resistance, Blows/Ft. 10    20    30    40    50												
	SURFACE ELEVATION 412.2 FT.																		
5	Brown Clay and Silty Clay with trace fine gravel (FILL)		2																
7.0	Gray Clayey Silt (FILL)																		
10	Gray medium stiff Clayey Silt (ML)	9.2	5																
12.0	Brown mottled medium stiff Silty Clay (CL) with trace gravel		2																
15			3																
17.5	Brown very stiff Clay (CH) with some gravel		6																
20			12																
20.5	Weathered Limestone and Chert	21.0																	
21.0	Light gray and tan thin- to medium-bedded fine-grained crystalline Limestone with intermittent chert and occasional weathered partings																		
25	-4.5 in. clay seam at 24.3 feet		ROD 50		93														
30			45		100														
35	Boring terminated at 36.0 feet		37		93														

WATER LEVEL OBSERVATIONS		NOTES
DURING DRILLING	17.5 FT.	Hard coring: 36 minutes to advance core barrel 4 inches at 28.5 feet.
AT COMPLETION	FT.	
AFTER	HRS. FT.	

Shear Test Types - Direct Shear: ● Torvane: ■ Unconf. Compr.: ▼ Miniature Vane: ▲ Field Vane: ◆

MIDWEST TESTING

Old Highway 141 Bridge  
Fenton, Missouri

**LOG OF BORING 2**

PROJECT NO. 10395      DATE: 3/9/04      LOCATION: See Figure 1

DEPTH, FT.	COMPLETION DEPTH 23.0 FT.	STRATUM DEPTH, FT.	SPT BLOWS/6 in. THREE 6-in. INCREMENTS	DISTURBED SAMPLE	PERCENT RECOVERY	ROCK CORE	Shear Strength from Indicated Test, tsf												
							1	2	3	4	5								
	BORING METHOD CFA-RC						Dry Density, pcf 80    90    100    110    120												
	ROCK CORE DIAMETER    IN.						Plastic Limit    Water Content, %    Liquid Limit Standard Penetration Resistance, Blows/Ft. 10    20    30    40    50												
	SURFACE ELEVATION 414.8 FT.																		
5	5 in. Asphalt 4 in. Crushed Stone Brown mottled medium stiff Silty Clay (CL)		2																
4.5	Brown medium stiff Clay (CH) with trace gravel		3																
7.5	Weathered Limestone and Chert	8.0																	
10	4 in. Gray Limestone 9 in. Brown Clay with trace sand 7 in. Gray Limestone 12 in. Gray Clay with trace sand Light gray and tan thin- to medium-bedded fine-grained crystalline Limestone with intermittent chert and occasional weathered partings	10.7																	
15			ROD 55		83														
20			56		93														
25	Boring terminated at 23.0 feet	23.0																	

WATER LEVEL OBSERVATIONS		NOTES
DURING DRILLING	Dry FT.	
AT COMPLETION	FT.	
AFTER	HRS. FT.	

Shear Test Types - Direct Shear: ● Torvane: ■ Unconf. Compr.: ▼ Miniature Vane: ▲ Field Vane: ◆

MIDWEST TESTING

WOOLPERT INC  
4454 IDEA CENTER BLVD.  
DAYTON, OHIO 45430  
937.461.5660

**OLD HIGHWAY 141  
ROADWAY IMPROVEMENT PLANS**  
FENTON, MISSOURI  
Prepared For:  
**CITY OF FENTON**

REVISIONS NO.	DATE

ENGINEERS AUTHENTICATION  
The responsibility for professional engineering liability on this project is hereby limited to the set of plans authorized by the seal, signature, and date hereunder attached. Responsibility is disclaimed for all other engineering plans involved in this project and specifically excludes revisions after this date unless reauthorized.

WOOLPERT, LLP  
MICHAEL A. AVELLANO  
NUMBER 228747  
APRIL 12 2010

DRAWN	DATE
RACH	APRIL-2010
CHECKED	DATE
B.W.B.	APRIL-2010
PROJECT #	061923
TASK #	01 FIELD BOOK

OLD HIGHWAY 141  
ROADWAY IMPROVEMENT PLANS  
SOIL BORING LOGS  
**SHEET B-17**  
© Copyright 2004 by Woolpert, LLP

PRINTED Apr 01, 2010 - 11:13am FILENAME - G:\FD\Clients\Bridges\City of Fenton, Ill (Old 141)\CAD\B17-502.dwg



**Re: BRM 4989(606) Local Roads Project Contractor Initiated FINAL VE** 

**David M Koenig** to: David J Simmons

04/14/2011 10:59 AM

Cc: Jeffrey J Aholt, Gregory G Sunde, James E Smith

History: This message has been replied to and forwarded.

We reviewed the submitted information and only have one question. Did the specifications for the project get updated as part of this VE proposal? If so, then we will need a copy of the updated specifications submitted for our records. We are okay with the project going ahead and moving forward. If you need anything else, please let me know. Thanks.

**David Koenig**  
**Structural Services Engineer**  
**MoDOT-Bridge Division**  
**573-526-0556**

David J Simmons    [Mr. Koenig, Please review the Final VECP rega...](#)    04/13/2011 01:22:21 PM

From: David J Simmons/D6/MODOT  
To: David M Koenig/SC/MODOT@MODOT  
Date: 04/13/2011 01:22 PM  
Subject: BRM 4989(606) Local Roads Project Contractor Initiated FINAL VE

Mr. Koenig,

Please review the Final VECP regarding this project. I have attached all of the information I received. There was a change in the footing type from the original Conceptual Proposal.

Please let me know if you have any questions.

[attachment "BRM-4989(606)\_FinalVE.pdf" deleted by David M Koenig/SC/MODOT]

Thanks,

Dave

**David J. Simmons P.E.**  
**Senior Construction Inspector**  
**Local Roads Division**  
**314-220-6621**

David M Koenig    [Bridge Division is okay with the conceptual prop...](#)    02/16/2011 04:11:31 PM

From: David M Koenig/SC/MODOT  
To: Richard T Miller/SC/MODOT@MODOT  
Cc: Andrew T Mueller/D8/MODOT@modot, David J Simmons/D6/MODOT@modot, david.morris@dot.gov, James E Smith/SC/MODOT@modot, Jeffrey J Aholt/SC/MODOT@MODOT  
Date: 02/16/2011 04:11 PM  
Subject: Re: Fw: BRM 4989(606) Local Roads Project Contractor Initiated VE Proposal

Bridge Division is okay with the conceptual proposal as specified in the attached documents. The contractor will need to address the items listed below for approval of the final proposal by Bridge Division. The contractor will also have to address any concerns of the engineer of record for the project as well as the city of Fenton. The updated deliverables for Items 1, 2, 3, and 4 will need to be submitted to Bridge Division. They can be submitted in an electronic PDF format provided that all of the documents are signed and sealed in accordance with State law.

1. A new Structure Inventory & Appraisal Sheets (SI&A) sheet will have to be submitted for the changed structure. The majority of the items will remain the same, but the engineer for the contractor will have to review the SI&A for the structure based on the original plans and update it accordingly.



**Re: Fw: BRM 4989(606) Local Roads Project Contractor Initiated FINAL VE**

**Glenn Smith** to: David.J.Simmons

04/15/2011 11:16 AM

Cc: "Tim Nugent", "Dan Howard", David.Koenig

---

David: No project specification revisions were made or needed as part of this VE. THANKS,  
GLENN

*PS Dave Koenig: I don't know if you remember, but I was one of the guys you met at the recent TEAM conference and we exchanged cards at the Concrete Pipe social hour.*

Glenn A. Smith, P.E.

CDG Engineers

1 Campbell Plaza

St. Louis, MO 63139

[gsmith@cdgengineers.com](mailto:gsmith@cdgengineers.com)

Office Direct: 314-446-3535

Mobile: 314-620-4991

>>> <David.J.Simmons@modot.mo.gov> 4/14/2011 2:35 PM >>>

Would you please help me out with this request/question?

Thanks,

Dave

**David J. Simmons P.E.**

**Senior Construction Inspector**

**Local Roads Division**

**314-220-6621**

----- Forwarded by David J Simmons/D6/MODOT on 04/14/2011 02:34 PM -----

From: David M Koenig/SC/MODOT

To: David J Simmons/D6/MODOT@MODOT

Cc: Jeffrey J Aholt/SC/MODOT@MODOT, Gregory G Sunde/SC/MODOT@MODOT, James E Smith/SC/MODOT@MODOT

Date: 04/14/2011 10:59 AM

Subject: Re: BRM 4989(606) Local Roads Project Contractor Initiated FINAL VE

---

We reviewed the submitted information and only have one question. Did the specifications for the project get updated as part of this VE proposal? If so, then we will need a copy of the updated specifications submitted for our records. We are okay with the project going ahead and moving forward. If you need anything else, please let me know. Thanks.

**David Koenig**

**Structural Services Engineer**

**MoDOT-Bridge Division**  
**573-526-0556**

From: David J Simmons/D6/MODOT  
To: David M Koenig/SC/MODOT@MODOT  
Date: 04/13/2011 01:22 PM  
Subject: BRM 4989(606) Local Roads Project Contractor Initiated FINAL VE

---

Mr. Koenig,

Please review the Final VECP regarding this project. I have attached all of the information I received. There was a change in the footing type from the original Conceptual Proposal.

Please let me know if you have any questions.

[attachment "BRM-4989(606)\_FinalVE.pdf" deleted by David M Koenig/SC/MODOT]

Thanks,  
Dave

**David J. Simmons P.E.**  
**Senior Construction Inspector**  
**Local Roads Division**  
**314-220-6621**

From: David M Koenig/SC/MODOT  
To: Richard T Miller/SC/MODOT@MODOT  
Cc: Andrew T Mueller/D8/MODOT@modot, David J Simmons/D6/MODOT@modot, david.morris@dot.gov, James E Smith/SC/MODOT@modot, Jeffrey J Aholt/SC/MODOT@MODOT  
Date: 02/16/2011 04:11 PM  
Subject: Re: Fw: BRM 4989(606) Local Roads Project Contractor Initiated VE Proposal

---

Bridge Division is okay with the conceptual proposal as specified in the attached documents. The contractor will need to address the items listed below for approval of the final proposal by Bridge Division. The contractor will also have to address any concerns of the engineer of record for the project as well as the city of Fenton. The updated deliverables for Items 1, 2, 3, and 4 will need to be submitted to Bridge Division. They can be submitted in an electronic PDF format provided that all of the documents are signed and sealed in accordance with State law.

1. A new Structure Inventory & Appraisal Sheets (SI&A) sheet will have to be submitted for the changed structure. The majority of the items will remain the same, but the engineer for the contractor will have to review the SI&A for the structure based on the original plans and update it accordingly.

2. Because of the change in the structure, a new load rating will be required.